


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Frank W. Campbell under Contract No. 380 dated March 19, 1881:

Set Pine Post from which

- Pine, 20" Dia., BRS. S57°E., 75 Lks. Dist.
- Pine, 10" Dia., BRS. S38°W., 9 Lks. Dist.
- Pine, 15" Dia., BRS. N75°E., 13 Lks. Dist.
- Pine, 11" Dia., BRS. N22°W., 11 Lks. Dist.



Description of corner evidence found:

Found (BRG. and DIST from re-established corner point; original post is now gone).

Ponderosa Pine, 22" Dia., BRS. S57°E., 49.5 Ft. Dist. with scribing visible on open face.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:
From which new BTs

Douglas Fir, 14" Dia., BRS. N36 3/4°E., 67.5 Ft. Distance.
Marked: T6S R30E S8 BT

Douglas Fir, 11" Dia., BRS. S42°W., 21.7 Ft. Distance.
Marked: T6S R30E S18 BT

Douglas Fir, 9" Dia., BRS. N38 3/4°W., 17.9 Ft. Distance.
Marked: T6S R30E S7 BT

6' Iron Fence Post with "Attention" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped: PLS 345; nailed to lower blaze.

T6S R30E
<u>S7 S8</u>
S18 S17
1979
PLS 346

Office of County Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of .
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
 Date 10-17-79
 Rec'd By MJL
 No. Q-1171-B

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Wayne O. Harris

**OREGON
MAY 6, 1955
WAYNE O. HARRIS
346**

J-5