


History of original corner establishment:

The original corner was established by Rufus S. Moore on June 7, 1881, under GLO contract No. 382, as follows: Set a post for the corner to townships 6 & 7 south and ranges 32 & 33 east, from which: A 20" Yellow Pine bears N76°E, 31 links (20.46 feet). A 16" Tamarack bears N8°W, 34 links (22.44 feet). A 26" Yellow Pine bears S37°W, 27 links (17.82 feet). A 24" Yellow Pine bears S27°E, 145 links (95.7 feet).



In 1967, the BLM recovered the following evidence of the corner: A 20" pine with a healed blaze bears N76°E, 31 links. A 26" pine with visible scribes bears S37°W, 27 links. A 21" larch with visible scribes bears N8°W, 34 links. The BLM set a 2 1/2" iron post at the corner point with a brass cap attached marked as shown in the diagram above, from which a 15" fir bears S15°30'E, 76 links (50.16 feet).

Description of corner evidence found:

A 2 1/2" iron pipe with a 3 1/4" brass cap attached. The cap is 3" above the ground and marked with the BLM logo and as shown in the diagram above, from which: A 21" Ponderosa Pine with double healed blazes bears N76°E, 20.1 feet. A 26" charred Ponderosa Pine snag, 40 feet tall, with charred scribes visible on upper blaze, lower blaze healed, bears S40°W, 19.3 feet. A 21" Western Larch with scribes visible on a previously opened upper blaze, lower blaze healed, bears N8°W, 23.2 feet. The fir scribed by the BLM in 1967 is down and badly burnt. I cannot determine where it stood.

Description of monument and accessories I established to perpetuate the

original location of this corner:

I establish the following new bearing trees:

A 11" Douglas-fir scribed "T7S R33E S6 BT" on double blazes bears S10°45'E, 72.9 feet.

A 21" Douglas-fir scribed "T7S R32E S1 BT" on double blazes bears S50°W, 77.2 feet.

Both trees have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze and a 54-3, "Bearing Tree", sign nailed above the blazes and a 54-9, "Land Survey Monument", sign nailed to the back.

I hereby certify the above corner was perpetuated as hereon described on March 7, 1997. Magnetic declination: 20°E.



Office of... County of... I hereby certify that the within instrument was filed in this office for record on the 7th day of March, 1997 by... (DEPUTY)

A-25

RECEIVED BY Umatilla County Surveyor Date 3-97 Rec'd By AK No. 97-40-R