


History of original corner establishment:

Corner position originally established by Frank Campbell in 1884. The original corner position was remonument from evidence of the original survey by Dennis Gaylord, ORE LS 1636: At the corner point: Set a 2 1/2"x30" iron pipe, 20" in the ground in a mound of stones, with 3" brass cap attached, marked:

From which:	T5S R32E
A 10" Fir bears S 13°E 112 links	S 32
(79.9 ft.) scribed T6S R32E S4 CC BT.	S5 S4
A 16" Fir bears S 40°W 137 links	CC
(90.4 ft.) scribed T6S R32E S5 CC BT.	T6S R32E
	LS 1636
	1982



Description of corner evidence found:

Found a 2 1/2" iron pipe, firmly set, with brass cap marked as described in the Gaylord Record (refer to Umatilla Co. Surveyor's Record No. 82-102-R), from which: The stumps of the original Campbell BT's exist as described in the Gaylord record, And BT's marked by Gaylord,
A 10" Douglas Fir bears S 13°E 73.9 ft. This tree is alive and in good condition, it does not appear to have been marked as described in the Gaylord record.
And a 16" Douglas Fir, alive with partially healed blaze bears S 40°W 90.4 links.

Description of monument and accessories established to perpetuate the original location of this corner:

We scribe the SE Gaylord BT as follows, scribed "CC T6S R32E S4 BT" on a double blaze, attached a brass washer marked LS 1099 to lower blaze.

September 7, 1984

Witnesses:

Gary Langlitz, LS 1099
Ray Crapo
Greg Orton



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 7 day of October, 1984
David Krumbein by B. Cochran
 (COUNTY OFFICIAL) (DEPUTY)

A-9