

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

The original corner was established by Frank W. Campbell on June 3, 1883, under GLO contract No. 468, as follows: Set a basalt stone 16" x 12" x 8" for the corner from which: A 18" tamarack bears N35°E, 14 links (9.24 feet). A 11" pine bears S65°E, 94 links (62.04 feet). A 24" pine bears S15°W, 84 links (55.44 feet). A 7" pine bears N10°W, 7 links (4.62 feet). In 1968, the BLM, under groups No. 350 and 643, found a down pine with full scribes visible for section 24. The root hole bears N10°W, 7 links. The BLM set a 2 1/2" iron post with a brass cap attached marked as shown in the diagram above, from which: A 24" pine bears N63°1/2 E, 85 links (56.1 feet). A 31" pine bears S50°W, 48 links (31.68 feet). A 23" pine bears N20°W, 18 links (11.88 feet). A 15" pine bears S15°1/2 E, 225 links (148.5 feet). On October 31, 1986, Fayette S. Munro, PLS 1832, found the BLM brass capped iron pipe in satisfactory condition with the cap marked as shown in the diagram above. Munro found a 23" Ponderosa Pine N17°1/2 W, 11.9 feet. A down and rotted Ponderosa Pine with visible scribes 4 feet to the northwest. A 36" uprooted Ponderosa Pine, root hole bears S50°W, 31.7 feet. A 30" uprooted Ponderosa Pine, root hole bears N63°1/2 E, 56.1 feet. A 17" Ponderosa Pine with visible scribes bears S2°E, 148.5 feet. Munro established the following new bearing trees: A 20" Ponderosa Pine bears N21°1/4 E, 111.3 feet. A 23" Ponderosa Pine bears S15°W, 94.2 feet.

DIAGRAM:

T6S	
R32E	R33E
S24	S19
S25	S30
1968	

DESCRIPTION OF CORNER EVIDENCE FOUND:

A 2 1/2" iron pipe with a 3 1/4" brass cap attached which is marked with the BLM logo and as shown in the diagram above. The cap is protruding 4" above the ground and is surrounded by a mound of stones, from which: A burnt out root hole, all that remains of the original bearing tree to the northwest bears N10°W, 4.6 feet. A down and badly burnt Ponderosa Pine, no marks remain, root hole bears N64°E, 56.1 feet. A down and badly burnt Ponderosa Pine, no marks remain, root hole bears S50°W, 31.7 feet. A 23" Ponderosa Pine snag with charred scribes visible bears N17°W, 11.9 feet. A 18" Ponderosa Pine snag with a healed blaze bears S2°E, 148.2 feet. A 23" Ponderosa Pine snag with charred scribes visible bears S15°W, 94.5 feet. A 20" Ponderosa Pine snag with charred scribes visible bears N21°E, 110.9 feet.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

New references:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S19", attached at ground level, bears N75°45'E, 116.9 feet.
 A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S30", attached at ground level, bears S17°30'E, 73.9 feet.
 A 5/8" x 36" iron rod set 32" into the ground with a 3/4" brass washer, marked "PLS 1636 S25", attached at ground level, bears S43°W, 53.5 feet.
 A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S24", attached at ground level, bears N54°45'W, 71.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 26, 1997. Magnetic declination: 20° E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews 6/30/97

RECEIVED BY

Umatilla County Surveyor

Date 4-97

Rec'd By KK

No. 97-72-R