

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T-5

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set a pine post 3 ft long 3 ins square 24 ins in ground for 1/4 sec cor marked 1/4 S on W face from which:

- A Pine 10 ins dia brs S30°W 10 lks dist marked 1/4 S BT
- A Pine 5 ins dia brs N65°E 20 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.
Description of corner evidence found:

Found no evidence of the original GLO corner or its accessories.

Found a 1/2 inch diameter galvanized pipe 6 feet long driven 1 ft into the ground S10°W, 10 feet from the corner position as determined by survey. I removed this pipe and placed it next to the new aluminum corner monument described below.

See map of survey dated August, 1987.

Description of monument and accessories established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which;

- New BTs:
- A 15 inch diameter Douglas Fir bears N56°E, 98.21 feet marked 1/4 S29 BT
 - A 8 inch diameter Western Larch bears N2°W, 54.79 feet marked 1/4 S30 BT

I painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet West with 54-9 and 54-2 signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 14, 1987.

Witnesses: Greg Blackman, Rick Robinson and Jeff Petersen.



REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 10, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office for record on the 24 day of August 1987
David H. Chambers by Kathleen K. Chambers
(COUNTY OFFICIAL) (DEPUTY)

87-47-C