


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-1

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:




Set a granite stone 18x10x10 ins 12 inches in the ground for 1/4 sec cor marked 1/4 on W face from which:
 A pine 24 ins dia brs S62°E 49 lks dist marked 1/4 S BT
 A tamarack 12 ins dia brs N33°E 20 lks dist marked 1/4 S BT
 Corner remonumented in 1977 by Craig L. Wanless, BLM Group no. 350. His notes state; The 1/4 cor of secs 32 and 33, monumented with the original unmarked granite stone 18x10x10 ins firmly set 4 ins in the ground, from which the remains of the original bearing trees; A pine 32 ins diam, bears S55°E 53 lks dist with healed blaze. (record S62°E 49 lks). A sawed Larch stump 17 ins diam bears N22°W 20 lks dist with scribes visible (record N33°E). At the corner point set an iron post with brass cap marked; (markings shown below) from which new bearing tree: A pine 18 ins diam bears N29°W 37 lks dist marked 1/4 S32 BT.
 Deposit corner stone alongside iron post.

No record of subsequent monumentation found in Umatilla County survey records.
 Description of corner evidence found:

Found a standard BLM brass cap marked as shown:

Original BTs:

Found an 40 inch diam pine S55°E, 53 lks, live and vigorous with blaze evident.
 Found a 18 inch diameter Tamarack stump N22°W, 20 lks dist with scribes visible.



BLM BT:

Found a 20 inch diameter Pine N29°W, 37 lks dist, live and vigorous with scribes visible.

See map of survey dated August 1987.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a steel fencepost approximately 5 feet North with 54-2 and 54-9 sign attached.

Painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

I hereby certify that the above corner point was perpetuated as hereon described on July 29, 1987.

Witness: Rick Robinson



Office of Survey Dept. OR County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 24th day of August, 1987
David H. Robinson by Kathleen K. Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

87-47-c