

History of original corner establishment:

The original corner was established by Frank W. Campbell on July 1, 1883, under GLO contract No. 468 as follows: Set a granite stone, 18" x 10" x 10", from which: A 24" pine bears S62°E, 49 links (32.34 feet). A 12" tamarack bears N33°E, 20 links (13.2 feet). In 1977, the BLM, under Group No. 350, found the original unmarked stone, 18" x 10" x 10", and the following bearing trees: A 32" pine with a healed blaze bears S55°E, 53 links (34.98 feet). A 17" sawn Larch stump with scribe marks visible bears N22°W, 20 links (13.2 feet). The BLM set a 2 1/2" iron post with a brass cap attached marked as shown in the diagram, from which a new bearing tree: A 18" pine bears N29°W, 37 links (24.42 feet). On July 29, 1987, Duane I. Griffith, PLS 644, found the BLM brass capped monument as described above and the following bearing trees: A 40" pine bears S55°E, 53 links (34.98 feet). A 18" tamarack stump with scribes visible bears N22°W, 20 links (13.2 feet). A 20" pine with scribes visible bears N29°W, 37 links (24.42 feet). Griffith set a steel fence post 5 feet north of the corner monument.

DIAGRAM:

T6S R33E
1/4
S32|S33
1977

Description of corner evidence found:

A 2 1/2" iron pipe with a 3 1/4" brass cap attached which is marked with the BLM logo and as shown in the diagram above. The cap is protruding 3" above the ground, from which:
A 33" Ponderosa Pine snag with double healed blazes bears S54°E, 34.1 feet.
A badly burnt Western Larch stump, no marks remaining, bears N18°W, 13.2 feet.
A 22" sawn Ponderosa Pine stump with scribe marks, "BT", visible, bears N26°W, 24.8 feet.

Description of monument and accessories I established to perpetuate the original location of this corner:

New references:

A 36" Ponderosa Pine scribed "1/4 S33 BT" on double blazes bears N85°E, 184.3 feet. This tree has a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze and a 54-3, "Bearing Tree", sign nailed above the blazes and a 54-9, "Land Survey Monument", sign nailed to the back of the tree.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S33", attached at ground level bears S13°30'E, 53.5 feet.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S32 SW", attached at ground level bears S33°W, 70.1 feet.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S32 NW", attached at ground level bears N9°15'W, 82.1 feet.

I hereby certify the above corner was perpetuated as hereon described on March 25, 1997. Magnetic declination: 20°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews 6/30/97 X-9

RECEIVED BY

Umatilla County Surveyor
Date 4-97
Rec'd by KK
No. 97-78-R