


T. 6 S. R. 34 E.  
Merid. Willamette

R.D. North Fork John Day  
N.F. Umatilla

County Umatilla  
State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

A 3 1/4" aluminum cap solidly set flush to the ground surrounded by a small mound of stones.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

12" Fir Snag with burnt out blazes, S. 3 1/2 W., 24.9 feet.  
12" Lodgepole Pine Snag with charred scribes visible on double blaze, N 34 1/2 W., 8.7 feet.

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the jct. Of roads 5226 and 5226-200 travel northerly on 5226 approx. 0.92 miles. The corner is located uphill (westerly) approx. 200 feet from the road.

**PLANE COORDINATE POSITION DATA**

State: Zone:  
X:  
Y:  
Datum:

Signature

D. Gaylord

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/04/1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

6" Lodgepole Pine scribed "WB/162 BT" on double blaze, N. 70 1/2 E., 92.8 feet.

5/8" by 36" iron rod, set 35" into the ground with 3/4" brass washer "PLS 1636" attached at ground level, bears S. 22 W., 84.0 feet.

Work Done By D. Gaylord Title Land Surveyor Date 06/04/1997 State Registration No. or Agency \_\_\_\_\_  
Certified Corner Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index File No.

T. **6 S.**

R. **34 E.**

M. **W.M.**

Tract or Survey No. **Tower Unit**

Cor. **AP-162**

Index  
File No.

**CORNER RECORD (SEARCH)**  
(Ref. FSM 7151.4)

Tract or  
Survey No. Tower Unit


Cor.  
No. AP-162

T. 6 S. R. 34 E.  
Merid. WILLAMETTE

R.D. NFJD  
N.F. UMATILLA

County UMATILLA  
State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND  
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
NONE

PHOTO IDENTIFICATION DATA

Photo No.:  
Filed At.:  
Object Ident.:  
Ident. By:

*Signature*

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
From the jct. of FS rds. 5226 and 5226-200 travel northerly on 5226 approx. 0.92 miles.  
The corner is located uphill (westerly) approx. 200 feet from the road.

PLANE COORDINATE POSITION

State: Oregon Zone: North  
X: 2,499,254.43'  
Y: 514,837.96'  
Datum: NAD1927

Signature  
**D. Schlaich**

Title  
**Land Surveyor**

Division

Headquarters  
**S.O.**

Date  
**09-1993**

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 3/8" rebar, with a 3 1/4" aluminum cap, 33" in the ground surrounded by a small stone mound 1' in diameter, marked "NFJD WILDERNESS TOWER UNIT AP-162 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" Lodgepole Pine, N. 35° W., 8.6 ft., mkd. "WB/162"BT" on double blaze.

12" Alpine Fir, S. 3 1/2° W., 25.3 ft., mkd. "WB/162"BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-162