

Index
File No.

T. 6 S. R. 34 E.
Merid. WILLAMETTE


CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

R.D. NFJD County UMATILLA
N.F. UMATILLA State OREGON

Tract or
Survey No. Tower Unit

Cor.
No. AP-694

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:
Filed At.:
Object Ident.:
Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located on the ridge between North Fork Cable creek and Winom creek.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,481,962.07'
Y: 506,415.26'
Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS TOWER UNIT AP-694 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

13" Western Larch, S. 6° W., 38.4 ft., mkd. "WB/694" "BT" on double blaze.

12" Western Larch, N. 42° E., 27.1 ft., mkd. "WB/694" "BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 07-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Tower Unit

Cor.

AP-694