

USDA-FOREST SERVICE

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**  
(Ref. FSM 7151.4)


R.D. NFJD  
N.F. UMATILLA

County UMATILLA  
State OREGON

Tract or  
Survey No. Tower Unit

Cor.  
No. AP-410

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND  
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,502,857.46'

Y: 498,852.93'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
From the jct. of FS rds. 52 and 5226 travel northerly on 5226 approx. 3.37 miles. The corner is located approx. 200 northerly of the road in the saddle of a spur ridge.

*Signature*

D. Schlaich

*Title*

Land Surveyor

*Division*

*Headquarters*

S.O.

*Date*

06-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, 35" in the ground, marked "NFJD WILDERNESS TOWER UNIT AP-410 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

14" Western Larch, S. 83° E., 26.5 ft., mkd. "WB/410""BT" on double blaze.

17" Western Larch, S. 77 1/2° W., 27.6 ft., mkd. "WB/410"BT" on double blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 06-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-410