

USDA-FOREST SERVICE

Index  
File No.

T. 6 S. R. 34 E.  
Merid. Willamette

CORNER RECORD (SEARCH)  
(Ref. FSM 5151.4)

R.D. North Fork John Day  
N.F. Umatilla

County Umatilla  
State Oregon

Tract or Survey No. North Fork John Day Unit  
Cor. No. AP-614

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar with a 3 1/4" aluminum cap, projecting 4" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

9" Lodgepole Pine Snag, N. 67 1/2 E., 20.9 feet, with scribing visible on burnt double blaze.  
12" Western Larch, S. 10 1/2 W., 33.0 feet, with scribing visible on double blaze.

PHOTO IDENTIFICATION DATA

Photo No.  
Filed At.  
Object Ident.  
Ident. By  
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5200-440 travel southwesterly on road 5200-440 approximately 0.41 miles. Then walk southerly approximately 200 feet to the corner.

PLANE COORDINATE POSITION DATA

State: Zone:  
X:  
Y:  
Datum:

Signature  
D. Schlaich

Title  
Land Surveyor

Division

Headquarters  
S.O.

Date  
10/22/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" Western Larch, S. 1 E., 40.3 feet, scribed "WB/614" "BT" on double blaze.

Work Done By D. Schlaich

Title

Land Surveyor

Date 10/22/1997

State Registration No.  
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At

Date

REMARKS

Index

File No.:

T. 6 S.

R. 34 E.

Merid. WILLAMETTE

## CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. NFJD Unit

Cor.

No. AP-614


R.D. NFJD

County UMATILLA

N.F. UMATILLA

State OREGON

## CORNER DIAGRAM



## DESCRIBE CORNER MONUMENT FOUND

NONE

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

## PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

## DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5200-440 travel southwesterly on road 5200-440 approx. 0.41 miles. Then walk southerly approx. 200 feet to the corner.

## PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,482,399.22'

Y: 494,882.09'

Datum: NAD1927

*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-614 RLS 2308 1993".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

13" Western Larch, S. 13° W., 33.0 ft., mkd. "WB/614" "BT" on double blaze.

9" Lodgepole Pine, N. 74° E., 20.9 ft., mkd. "WB/614" "BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-614