

USDA-FOREST SERVICE  
Index  
File No.


**CORNER RECORD (SEARCH)**  
(Ref. FSM 5151.4)

Tract or Survey No. **North Fork John Dav Unit** Cor. No. **AP-642**

T. 6 S. R. 34 E.  
Merid. Willamette

R.D. North Fork John Day County Umatilla  
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3 1/4" aluminum cap, set flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

7" by 1 1/2' high Fir stub, S. 18 W., 71.6 feet, with burnt out blaze.  
9" Englemann Spruce, N. 61 3/4 W., 60.3 feet, with scribing visible on double blaze.

PHOTO IDENTIFICATION DATA

Photo No.  
Filed At.  
Object Ident.  
Ident. By \_\_\_\_\_  
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of road 52 and 5200-440 travel easterly on road 52 approximately 0.14 miles.  
Then walk southerly approximately 200 feet to the corner which is located in a draw.

PLANE COORDINATE POSITION DATA

State: \_\_\_\_\_ Zone: \_\_\_\_\_  
X:  
Y:  
Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquartes

S.O.

Date

10/23/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" Western Larch, S. 50 ¼ W., 73.8 feet, scribed "WB/642" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 10/23/1997 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_  
Certified Corner Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index

File No.

T. 6 S.

R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON

Tract or

Survey No. NFJD Unit

Cor.

No. AP-642

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES; ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5200-440 travel easterly on road 52 approx. 0.14 miles. Then walk southerly approx. 200 feet to the corner which is set in a draw.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,484,584.60'

Y: 495,421.27'

Datum: NAD1927

*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-642 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

9" Englemann Spruce, N. 58° W., 61.2 ft., mkd. "WB/642""BT" on double blaze.

6" Fir, S. 23° W., 71.6 ft., mkd. "WB/642"BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-642