

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

Tract or

Survey No. NFJD Unit


County UMATILLA

State OREGON

Cor.

No. AP-657

## CORNER DIAGRAM



## DESCRIBE CORNER MONUMENT FOUND

NONE

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

## PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

## PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,486,578.06'

Y: 494,386.72'

Datum: NAD1927

## DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5200-440 travel easterly on road 52 approx. 0.14 miles. Then walk southerly approx. 200 feet to a draw. Follow the draw southeasterly approx. 1900 feet to the confluence of the draw with Big creek. At this point ascend a spur ridge southeasterly approx. 800 feet to the corner set at an elevation of 5120 feet

*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT  
5/8" by 24" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-657 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE  
14" Lodgepole Pine, S. 71° W., 17.7 ft., mkd. "WB/657""BT" on double blaze.  
10" Lodgepole Pine, S. 19° E., 20.0 ft., mkd. "WB/657"BT" on double blaze.  
Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-657