


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-09

History of original corner establishment:

Original corner established in 1881 by Jacob C. Cooper under contract #397. Set a basalt stone, 14"x10"x6", 9" in ground. From which:  
A 20" Pine bears N58°E, 80 lks.  
An 18" Pine bears N65°W, 7 lks.



Description of corner evidence found:

Found original stone, 14"x10"x6" with 2 grooves on West and 4 grooves on East faces, firm in place. Found the following original bearing trees:  
A dead and down Pine slab with open blaze, full scribing visible, decayed stump bears N65°W, 7 lks.  
A dead standing 21" Ponderosa Pine, blaze chopped open, 'R35ES33' visible bears N60½°E, (orig. N58°E) 80 lks.

Description of monument and accessories I established to perpetuate the original location of this corner:

Cap is stamped:  
At the position of the original stone, I set a 2½"x30" aluminum capped aluminum pipe rising 8" in a mound of stones with original stone along N. side. I set a steel fence post 3' North of corner  
New BT's:  
An 11" Douglas Fir bears N13°E, 22.3 ft. blazed&scribed: T6SR35ES33BT  
A 13" W. Larch bears N69½°W, 71.7 ft., blazed and scribed: T6SR35ES32BT

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982. A ½" brass disk stamped "RLS 1848" was nailed to the lower end of the blazes. From Rd. 5200 take 5200610 NW'ly up draw 0.3 miles. Corner is North ½ mile, 300 ft. South of a NE-SW ridge, 150 ft. West of a shallow draw on Southerly slope.

Compass declination: 20½°E  
Witness: Jeremy Sutton

I hereby certify that the above described corner monument and/or accessories were established as hereon described on June 28, 1987.



Office of Survey Dept County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office for record on the 21<sup>st</sup> day of September 1987  
David A. Kumbier by Jeremy Sutton  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor  
Date 9-87  
Rec'd by [Signature]  
No. 87-52-R

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276