

USDA-FOREST SERVICE

Index

File No. A-19

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 7 S R. 34 E

R.D. NORTH FORK JOHN DAY County Grant

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND 2

No original Evidence

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER 3

Take Road 510 off 52 Road To 4"x4" post near 35/36
Go west to sec. cor. then West 1/2 mi. to 1/4 Cor, 211

5.35
S.2.

PHOTO IDENTIFICATION DATA 6

Photo No. 680-164

Filed At. PENDLETON

Object Ident. PRECISE

Ident. By _____
Signature

PLANE COORDINATE POSITION DATA 7

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

Signature

Clayton J. Martin

Title

Land Surveyor

Division

Headquarters

Date

10/25/56

FS-7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

set $2\frac{1}{2}$ " Diam. Cap on a $2\frac{1}{2}$ " X 30" Alum Pipe at proportioned
 corner. RAISED stone mound. Cap MKD. per sketch.
 set steel posts $4\pm$ E. & W. w/ATTN & MON. SIGNS Attached.

T65 R34E

$\frac{1}{4}$ $\frac{535}{52}$

T7S
 RPLS 1910
 1985

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

① 12" D.B.H. WHITE FIR, N. 83° W., 28.8', scribed $\frac{1}{4}$ S35BT.

② 6" D.B.H. Douglas Fir, S. 10° E., 32.8', scribed $\frac{1}{4}$ S2BT.

Set a brass washer MKD. RPLS 1910 Btwn. B & T on each Bt., set atn. signs, B.T. tags,
 painted bands and Faces Red.

10

Work Done By C.J. Martin Title Land Surveyor Date 10/24/86 State Registration No. L5 1910
 or Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

12

Index File No.
 A-19

T. 75. R. 34 E

M. WILLAMETTE Tract or Surv. No.

GPO: 1982 O-382-659

Cor.
 $\frac{1}{4}$ $\frac{25}{2}$

13