

USDA-FOREST SERVICE

Index

File No. C-19

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 7.5 R. 34 E R.D. NORTH FORK JOHN DAY County Grant

Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM



C4, S.2

DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estob. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Take Road 52 & 5 to 510, Go on 510 1/4 mile to C1/4 on left, about 300'± From Road

Signature

Clayton J. [Signature]

Title

Land Surveyor

Division

Headquarters

Date

10/25/86

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set $2\frac{1}{2}$ " Diam. Alum. Cap on a $2\frac{1}{2}$ " x 30" Alum. Pipe w/flare at bottom, at point for corner. Cap mkd. per sketch. Set steel posts $4\frac{1}{2}$ " N. & W. w/Prop. Bindry., Attn. and mon. signs attached.

T75 R34E

C4S2

RPLS 1910

1986

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

① 8" D.B.H. Lodgepole Pine, S. 5° W., 82.4', scribed C4S2 BT.

② 8" D.B.H. Lodgepole Pine, N. 57° E., 205.7', scribed C4S2 BT.

Set a brass washer mkd. RPLS 1910 Btwn. B. & T on each B.T., set B.T. Tags, Attn. signs, painted bands and faces red.

Work Done By C.J. Martin Title Land Surveyor Date 10/25/86 State Registration No. or Agency LS 1910

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No. C-19 T. 75 R. 34 E M. WILLAMETTE Tract or Surv. No. Cor. C 1/4