

Index

File No. **J-15**

T. 7 S.

R. 35 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. **NFJD UNIT**

Cor.

No. **AP-1397**


R.D. NFJD

County GRANT

N.F. UMATILLA

State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 2 1/2" aluminum pipe, with a 2 1/2" aluminum cap, projecting 1" out of a 2 ft. diameter ring of stone, marked "T7S R35E 1/4 S10 S15 1983 PLS 1106".

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

9" downed Lodgepole Pine snag, N. 25° W., 12.5 ft., with partially healed blaze (original BT).
 10" Douglas Fir, N. 15 1/2° E., 17.1 ft., scribing "4S10BT" visible on partially healed blaze, with a 3/4" brass washer mkd. "PLS 1106" nailed into lower circle of scribed "B".
 12" downed Lodgepole Pine snag, S. 49° W., 11.2 ft., scribing "S BT" visible on partially healed blaze (original BT).
 11" Douglas Fir, S. 61 1/2° W., 29.4 ft., scribing "1/4 S15 BT" on partially healed blaze, with 3/4" brass washer mkd. "PLS 1106" nailed into lower circle of scribed "B".

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and Forest trail 3021 travel westerly on the trail approx. 1.7 miles to the property line crossing. Then walk S. 1° 27' E., approx. 740 feet to the corner.

PLANE COORDINATE POSITION DATA

State:

Zone:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE
MARKED NEW BT:

5" Douglas Fir, S. 24° E., 17.7 ft., marked "1/4 S15""BT" on double blaze.

7" Douglas Fir, N. 52 1/2° W., 23.4 ft., marked "1/4 S10""BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared? **YES**

Filed At: **Grant County Surveyor's Office**

Date

REMARKS

Index File No.
J-15

T.
7 S.

R.
35 E.

M.
W.M.

Tract or Survey No.
NFSD UNIT

Cor.
AP-1397