

Index

File No. **J-19.14**

T. 7 S. R. 35 E.

Merid. WILAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County GRANT

State OREGON

Tract or

Survey No. NFJD Unit

Cor.

No. AP-1400

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION DATA

State: Zone:

Y:

Datum:

DESCRIBE CORNER MONUMENT FOUND

NONE.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE.

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5200-685 travel southeasterly on 5200-685 approx. 0.11 miles to the line between sections 12 and 13. Then walk N. $87\frac{3}{4}^{\circ}$ W., following the section lines, approx. 2960 feet to the corner which lies in the center of Trout Creek.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 19" into the center of Trout creek, marked "T7S R35E S11 NFJD S14 AP-1400 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

5/8" by 24" rebar, with 1 1/2" aluminum cap set 22" in the ground, N. 87°09' W., 67.20 ft., mkd. "USDA-FS S11 67.20 FT 2308".

5/8" by 24" rebar, with 1 1/2" aluminum cap set 21" in the ground, S. 35°09' E., 30.02 ft., mkd. "USDA-FS S14 30.02 FT 2308".

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **YES**

Filed At: **Grant County Surveyor's Office**

Date

REMARKS

Index File No.
J-19.14

T.

7 S.

R.

35 E.

M.

W.M.

Tract or Survey No.
NFJD Unit

Cor.
AP-1400