

Index

File No. M-21

T. 7 S. R. 35 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County GRANT

State OREGON

Tract or

Survey No. NFJD UNIT

Cor.

No. AP-1486

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION

State: Zone:

Y:

Datum:

DESCRIBE CORNER MONUMENT FOUND

Found a 2 1/2" aluminum pipe with 2 1/2" aluminum cap, projecting 3" out of the ground, marked "T7S R35E S1/16 S14 S13 1983 PLS 1106".

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

13" Windthrown Lodgepole Pine, N. 51° E., 30.1 ft., scribed "S1/16 S13 BT" visible on single blaze.

14" Windthrown Lodgepole Pine, N. 17° W., 37.1 ft., scribed "S1/16 S14 BT" on single blaze.

Both BT's have a 3/4" brass washer stamped "PLS 1106" nailed into the lower circle of the scribed "B".

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 51 and 52 travel northwesterly on 52 approx. 3.7 miles to the property line crossing. Then walk westerly, following the property line, approx. 2000 feet to the corner.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE
NEW REFERENCES

10" Lodgepole Pine, N. 70° E., 39.4 ft., mkd. "S1/16 S13""BT" on double blaze.

7" Lodgepole Pine, N. 89 1/2° W., 11.5 ft., mkd. "S1/16 S14""BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 10-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? YES

Filed At: Grant County Surveyor's Office

Date

REMARKS

Index File No.
M-21

T.

7 S.

R.

35 E.

M.

W.M.

Tract or Survey No.
NFJD UNIT

Cor.
AP-1486