

## FIELD NOTES OF ROAD No. 293 to VACATE.

Commencing at the S E corner of the SW $\frac{1}{4}$  of section 1 in township 3 North of Range 29 east, thence north through the center of sec 1 80 40 chains to the NE corner of the NW $\frac{1}{4}$  of Sec 1, thence east on township line 40.60 to the corner to township s 3 and 4 north ranges 29 & 30 E W M thence east along the tp line 43.50 to county road NW & SE at point 2.70 chs west of the NE corner of the NW $\frac{1}{4}$  of Sec 6 T 3 N R 30 E W M

I hereby certify that the foregoing field notes of Road No. 293 to vacate are correct as surveyed by me on the 25th day of Feb 1910

John W. Kimbrell, county surveyor of Umatilla county Oregon

## REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of viewing, surveying and laying out to vacate county road No. 293. To the Honorable county court of the state of Oregon for Umatilla county.

We, the undersigned board of county road viewers, heretofore instructed to view, survey, and vacate Road No. 293 submit the following report:

Pursuant to an order of the Honorable county court we met at the office of county surveyor in Pendleton, the 25 day of February 1910. We called to our aid W J Stockman, chairman; Scott Brown, chairman; J H Saling, flagman Dave Lavender, marker who were by the surveyor each duly sworn. We viewed, surveyed and vacated said Road No. 293 as specified in our order. We find said route unnecessary for the use of the public highway and would most respectfully recommend the petition to vacate be allowed and that the same be declared vacated and abandoned as a public highway of Umatilla county, Oregon.

John W Kimbrell, D. F. Lavender, W J Stockman, board of county road viewers. Filed March 3, 1910.

Frank Saling, Clerk, by R. T. Brown, Deputy

## FIELD NOTES OF ROAD No. 678

Commencing at a point 6.70 chains south of the NE corner of the NW $\frac{1}{4}$  of Sec 6 T 3 N R 30 E W M set post 4x4 inches 4 feet long 30' north of initial point marked R 678 dug pits and raised mound of earth around post. Thence south 1.50 chs dist A 1, thence S 56° 30' W 2.67 chs, 4.17 A 2, thence S 25° 30' E 5.14, 9.31 A 3; thence south 70.69, 80.00 1 miles, set post 4x4 inches 4 feet long marked 1 M dug pits and raised mound of earth around post; thence south 74.50 to the SE corner of the SW $\frac{1}{4}$  of sec 7 T 3 N R 30 E W M post 30' south of terminus, marked R T 678, dug pits and raised mound of earth around post.

I hereby certify that the above field notes of Road No. 678 as surveyed by me on the 25 day of Feb 1910 are correct.

John W. Kimbrell, county surveyor of Umatilla county, Oregon

## REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of viewing, surveying and laying out county road No. 678. To the Honorable county court of the state of Oregon, for Umatilla county.

We, the undersigned board of county road viewers, heretofore instructed to view, survey and locate Road No. 678 submit the following report:

Pursuant to an order of the Honorable county court we met at county surveyor office in Pendleton on the 25 day of February 1910. We called to our aid W J Stockman, chairman; Scott Brown, chairman; J H Saling, flagman and Dave Lavender, marker, who were by the surveyor each duly sworn. We viewed, surveyed and located said road No. 678 as specified in our order. We find said route practicable and would most respectfully recommend the petition be allowed and the same be established and declared a public highway of Umatilla county, Oregon. The cost of construction to place said road in condition for public travel will be about \$100.00 the damages to be sustained by property owners by reason of the establishment of said road will be nothing.

John W Kimbrell, D F Lavender, W J Stockman  
Board of county road viewers of Umatilla county, State of Oregon.

Filed March 3, 1910

Frank Saling, Clerk by R T Brown, Deputy

## FIELD NOTES OF ROAD No. 679

Commencing at the NE corner of the SE $\frac{1}{4}$  of Sec 21 T 4 N R 29 E W M set post 4x4 inches square 4 feet long 30 feet east marked R 679 dug pits and raised mound 4' base 18 inch high around post thence N 45° E 80 00 1 mile set post 4 inches square 4 feet long 30 feet to right marked 1 M dug pits and raised mound 4 feet base 18 inch high. thence N 45° E 30.60 chs dist A 1, thence north 40.00 70.60 A 2, thence east 9.40 80 00 2 M set post 4 inch quares 4 feet long 30 feet east marked 2 M dug pits & raised mound 4' base 18 inch high, thence 775 ditch, east 80 00 3 M set post to right marked 3M dug pits and raised mound 4 feet base 18 inch high thence east 70 00 R T at the NE corner of Sec 13 T 4 N R 29 E W M set post 4 inch square 4 feet long marked R T 679 dug pits and raised mound 4 feet base 18 inch high around post.

I hereby certify that the foregoing field notes are correct of Road No. 679 as surveyed by me.

John W Kimbrell, county surveyor for Umatilla county, Oregon.