

Field Notes of County Road N. 711.

I commence at the NW corner of Sec 4 T 4 N R 28 E W M. At a point 20 ft S and 20 ft W of aforesaid point I set a post 4 ft long 4 ins square, marked R 711; dug pits 18x18x12 ins N & S of post and raised mound of earth 18 ins, high 4 ft base around post, and thence following the section line south 80.00 chs to a point from which I set to the right 20 ft distant, a post 4 ft long 4 ins square marked 1 M dug pits 18x18x12 ins N & S of post, and raised mound of earth, 18 ins high 4 ft base, around post. Thence following the section line south 0.80 chs to irrigation ditch 12 lks wide.

" " " " " " 19.58 " " angle 1

" S 61° 37' W 11.84 chs to angle 2

" S 48° 31' W .00 " " " 3

" S 62° 47' W 8.00 " " " 4

" S 34° 32' W 8.16 " " " 5

" south 6.45 " " " 6

" S 36° 36' E 13.42 " " " 7

" S 30° 55' E 3.75 " a point from which I set to the left 20 ft distant a post, 4 ft long 4 ins square, marked 2 M dug pits 1'x18x12 ins N & S of post, and raised mound of earth, 18 ins high 4 ft base around post. Thence S 30° 55' E 6.06 chs to angle 8 thence S 15° 23' E 14.89 chs to line between secs 8 & 17 in said township and range, angle 9 thence east 5.45 chs to west end of county steel bridge from which I set 20 ft S & 25 ft W a post, 4 ft long, 4 ins square, marked R T 711 dug pits W & S of post and raised mound of earth, 18 ins high 4 ft base around post.

I hereby certify that the foregoing field notes of county Road No 711 are correct according to the survey made by me commenced on the 23rd day of May, 1911.

Geary Kimbrell,
County Surveyor.

Report of Board)
of) In the Matter of viewing, surveying and laying out Road No 711.
County Road Viewers)

To the Honorable County Court of the State of Oregon for Umatilla County.

We, the undersigned Board of County Road Viewers heretofore instructed to view, survey, and locate road No. 711, submit the following report:

Pursuant to an order of the Honorable County Court we met at the commencement point of said road on the 23th day of May, 1911. We called to our aid

W J Stockman Chairman
Mr Dishon Chairman
L C Rothrock Flagman
Geary Kimbrell Marker

who were by the Surveyor each duly sworn. We viewed surveyed and located said road No 711, as specified in our order. We find said route practicable and would most respectfully recommend that the same be declared and established as a public highway of Umatilla County, Oregon.

The cost of construction will be for one bridge with concrete abutments about \$50.00

The damages to be sustained by property owners, by reason of the location and establishment of said road will be nothing.

Geary Kimbrell Board of County
W J Stockman Road viewers of
L C Rothrock. Umatilla County
State of Oregon.

Field Notes of County Road No 712

I commence at the $\frac{1}{4}$ sec corner on the north side of Sec 5 T 4 N R 28 E W M. At a point 20 ft S and 20 ft W of aforesaid point, I set a post, 4 ft long, 4 ins square marked R 712; dug pits, 18x18x12 ins N & S of post, and raised mound of earth, 18 ins high 4 ft base around post. Thence following the subdivisional section line south 80.00 chs to a point from which I set to the right 20 ft distant a post 4 ft long 4 ins square marked 1 M dug pits 18x18x12 ins, N & S of post and raised mound of earth, 18 ins high 4 ft base around post.

Thence South 1.10 chs to the $\frac{1}{4}$ sec corner between Secs 5 & 8 angle 1. Thence west 79.90 chs to a point from which I set to the right 20 ft. distant a post 4 ft long 4 ins square marked 2 M dug pits 18x18x12 ins N & S of post and raised mound of earth 18 ins high 4 ft base around post. Thence West 7.60 chs to irrigation canal 25 lks wide, course north. Thence west 45.42 chs to the S W corner of Sec 6 in said township and range from which I set 20 ft N & 20 ft E a post 4 ft long 4 ins square marked R T 712. dug pits E & W of post, and raised mound of earth, 18 ins high 4 ft base around post.

I hereby certify that the foregoing field notes of county Road No 712 are correct according to survey made by me, commenced on the 23rd day of May, 1911.

Geary Kimbrell
Surveyor of Umatilla County, Oregon.