

FIELD NOTES OF COUNTY ROAD NO. 706,

I commence at a point 227 ft. N of the SW corner of the NW 1/4 of the NW 1/4 of Sec 3, T 4 N R 28 E W M. At a point 33 ft. W of aforesaid point I set a post, 4 ft. long 4 ins. square, marked R 706: dug pits 18 x 18 x 12 ins. N & S of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence N 56° 5' E 262 lks. O R and N Co's railway track; 459 lks. to a point 30 ft. East of the East line of the O R and N Co's right of way, to Angle 1. Thence N 33° 55' W 17.91 chs. to a point due south of the SW corner of the SE 1/4 of the SE 1/4 of Sec. 33 T 5 N R 28 E W M. Angle 2. Thence North 1.96 chs. to the said SW corner of the said SE 1/4 of the SE 1/4 of Sec 33. Thence following the subdivisional section line north 20.13 chs. to the NW corner of the SW 1/4 of the SW 1/4 of said Sec 33 Angle 3. Thence N 18° 45' W 36.41 chs. to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 x 18 x 12 ins., N & S of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. 6120 chs. to the 1/4 sec corner between Sec's. 28 and 33 in said township and range Angle 4. Thence North 55.11 chs. to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M; dug pits, 18 x 18 x 12 ins. N and S of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. 79.84 chs. to the 1/4 sec. corner between Secs. 21 and 28 in said township and range from which I set, 30 ft. S and 30 ft. W a post, 4 ft. long, 4 ins. square, marked R T dug pits S & W of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County Road No. 706 are correct as surveyed by me on the 20th day of May, 1911.

Geary Kimbrell
Surveyor for Umatilla County, Oregon.

REPORT OF BOARD OF COUNTY ROAD VIEWERS.

In the Matter of Viewing, Surveying and laying out County Road No. 707.

To the Honorable County Court of the State of Oregon, for Umatilla County.

We, the undersigned Board of County Road Viewers, heretofore instructed to view survey, and locate Road No. 707, submit the following report:

Pursuant to an order of the Honorable County Court, we met at the commencement point of said road on the 20th day of May, 1911.

We called to our aid

W J Stockman, Chainman
L C Rothrock, Chainman
Geary Kimbrell, Marker

who were by the surveyor each duly sworn. We viewed, surveyed and located said Road No. 707, as specified in our order. We find said route practicable and would most respectfully recommend that the same be declared and established as a public highway of Umatilla County, Oregon, as follows; Beginning at the commencement point of said road and ending at the present County road, the SW corner of Sec 34 T 5 N R 28 E W M., The cost of construction will be nothing. The damage to be sustained by property owners, by reason of the location and establishment of said road will be nothing.

Geary Kimbrell
W J Stockman
L C Rothrock

Board of County Road Viewers of Umatilla
County, State of Oregon.

Approved and road ordered opened this 6th day of October, 1911.

J W Maloney, County Judge
H M Cockburn, County Com.

Filed June 8, 1911
Frank Saling, Clerk.

FIELD NOTES OF COUNTY ROAD NO. 707.

I commence at a point on the section line between secs. 3 and 4 227 ft. N of the SW corner of the NW 1/4 of the NW 1/4 of Sec. 3 T 4 N R 28 E W M. At a point 33 ft. W. of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R 707: dug pits, 18 x 18 x 12 ins. N and S of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence N 56° 5' E 2.62 chs. O R and N Co's railway track.

Thence 9.05 chs. to Angle 1

Thence N 24° E 5.50 chs. to Angle 2

" N 5° 35' E 2.95 " " " 3

" N 25° 41' E 4.69 " " " 4

" N 52° 10' E 1.82 " " " 5

Angle 5, North 55.99 chs. to a point from which I set, to the right, 33 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 x 18 x 12 ins. N and S of post and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence North 7.11 chs. to angle 6

" N 10° 40' E. 2.47 chs. to angle 7

" N 12° 50' W 4.54 " " " 8

" N 5° 40' E 3.88 " " " 9

" 38° E 3.07 " " " 10

" N 6° 20' W. 14.57 " " " 11

" N. 66° W 6.76 " " " 12

" N. 16° 20' E 3.80 " " " 13

" N. 28° 44' E 16.90 " " " 14

" N. 11° 33' E 10.59 " " " 15

Thence North 0.90 chs. to irrigation ditch 15 lks. wide 4.80 chs. to angle 16.