

REPORT OF BOARD OF COUNTY ROAD VIEWERS

In the Matter of viewing, surveying, and laying out County Road No. 754.

To the Honorable County Court of the State of Oregon, for Umatilla County.

We, the undersigned, Board of County Road Viewers, heretofore instructed to view, survey, and locate Road No. 754, submit to the following report:

Pursuant to an order of the Honorable County Court, we met at the Commencement of said Road, on the 29th day of July 1913.

We called to our aid

- L.C. Rothrock, Chairman
- Lowell Stockman Chairman
- W.J. Stockman Chairman
- Geary Kimbrell Marker

who were by the Surveyor each duly sworn. We viewed, surveyed and located said Road No. 754 as specified in our order. We find said route practicable and would most respectfully recommend the same be established and declared a public highway of Umatilla County, Oregon. The cost of construction of said road will be about \$150.00

The lands of Bertha B. Gurnsey, to, wit: the NE 1/4 of the SE 1/4 of Sec. 18 T, 5 N R. 28 E.W.M. will be damaged by reason of the location and establishment of said road in the sum of Nothing.

The lands of R.N. Stanfield to, wit: The NW 1/4 of the SW 1/4 of Sec. 17, T, 5 N.R. 28 E.W.M. will be damaged by reason of the location and establishment of said road in the sum of Nothing.

The lands of the Western Land and Irrigation Company to, wit: the S, W, 1/4 of the SW 1/4 of Sec. 17 and the W 1/2 of Sec. 29 T, 5 N.R. 28 E.W.M. will be damaged by reason of the establishment of said road in the sum of nothing.

The land of To, wit: The W 1/2 of the W 1/2 Sec, 20 and the W 1/2 of the W 1/2 of Sec, 32 1/2 N.R. 28 E.W.M. will be damaged by reason of the location and establishment of said Road in the sum of nothing.

- Geary Kimbrell
- L.S. Rothrock
- W.J. Stockman
- Board of County Road Viewers of Umatilla County,
- State of Oregon.

Filed Sept. 3, 1913

Frank Saling, Clerk By P.T. Brown, Deputy.

Approved and road ordered opened this 5th day of Sept. 1913,

- J.W. Maloney County Judge
- F.M. Cockburn, County Com.

FIELD NOTES OF COUNTY ROAD NO. 754.

I commence at a point on the first standard parallel north 1320 feet east of the southwest corner of section 32 T. 5 N.R. 28 E.W.M at a point 25 ft North and 30 ft. west of aforesaid point 1 set a post, 4 ft, long, 4 ins square, marked R. 754; dug pits 18x18x12 ins N. & S of post, and raised mound of earth, 18 ins, high, 4 ft, base, around post.

Thence following the subdivisional section line north 80.00 chs. to a point from which I set to the left 30 ft. distant, a post, 4 ft, long 4 ins. square, marked 1 M; dug pits 18x18x12 ins. North and south of post, and raised mound of earth 18 ins, high, 4 ft base, around.

Thence continueing north 160.00 chs. to a point from which I set to the left 30 ft. distant, a post, 4 ft, long, 4 ins. square, marked 2 M; dug pits, 18x18x12 ins North and south of post, and raised mound of earth, 18 ins, high, 4 ft, base, around post.

Thence continueing north 240.00 chas. to a point from which I set to the left 30 ft. distant, a post 4 ft, long, 4 ins. square, marked 3 M; dug pits, 18x18x12 ins. north and south of post, and raised mound of earth, 18 ins high 4 ft. base, a round post.

- Thence N. 26°28' W. 4.71 chs., to 244.71 chs.
- " N. 20°28' W. 6.06 " 250.77 "
- " N. 16°50' W. 5.70 " 256.47 "
- " N. 51°17' W. 4.64 " 261.11 "
- " N. 69°11' W. 3.44 " 264.55 "
- " N. 28° 2' W. 0.50 " 265.05 " To cen. Irrigon Ditch 35 lks wide
- " N. 23° 2' W. 0.43 " 265.48 "
- " N. 60°39' W. 3.25 " 268.83 "
- " N. 67° 7' W. 6.48 " 275.31 "
- " N. 56°45' W. 6.27 " 281.58 "
- " N. 41°53' W. 6.50 " 288.08 "

Thence N. 38°22' E. 0.80 chs. to 288.88 chs! the center of the west end of the County bridge across the Umatilla River, a point S. 53°W. 662 feet from the 1/4 section corner between sections 17 and 18 in aforesaid township and range, where I set to the right 30 ft. a post 4 ft, long 4 ins. square, marked R.T. 754; dug pits, 18x18x12 ins. north and south of post and raised mound of earth, 18 ins. high 4 ft. base around post.

I hereby certify that the foregoing field notes of County Road No. 754 are correct according to survey made by me on the 29th day of July 1913.

Geary Kimbrell County Surveyor.