

UMATILLA COUNTY, OREGON

FIELD NOTES

County Road No. 835.....

Date August, 1926.....

STATION	Curve Data	Length of Tangents and Curves	Bearing	REMARKS
0+00		890.2	South	Which point is coincident with the Northwest corner of the Southwest quarter of the Southwest quarter of section 18, T. 6 N., R. 35 E. W. M.
8+90.2 P.I.	$\Delta = 76^{\circ} 52' L.$	1286.3	S. 76° 52' E.	
21+76.5 P.C.	24° C.R. $\Delta = 35^{\circ} 50'$	149.3		
23+25.8 P.T.		0.1	S. 41° 02' E.	
23+25.9 P.C.	35° C.L. $\Delta = 49^{\circ} 07'$	140.5		
24+66.4 P.T.		1171.7	N. 89° 51' E.	
36+38.1 P.I.	$\Delta = 0^{\circ} 22' R.$	2643.9	S. 89° 47' E.	Which point is coincident with the one fourth section corner common to sections 18 and 19.
62+82.0 P.O.T.		1325.5	S. 89° 47' E.	Which point is coincident with the section corner common to sections 17, 18, 19 and 20.
76+07.5				End of Project, which point is coincident with the Southeast corner of the Southwest quarter of the Southwest quarter of section 17, T. 6 N., R. 35 E. W. M.