

To the Hon County Court,  
Umatilla County, State of Oregon.

I herewith submit Field Notes and  
Plat of Road Survey No 387:-

I met George Dehaven, Henry Frazier and  
Ransom Wells, viewers, at Milton, Oregon, on  
Wednesday April 20<sup>th</sup> 1892, and administer  
to each the usual Road viewers oath.

We called to our aid J. C. Still, J. C. Had-  
gen and J. W. Hodgen, as assistants and  
I administered oath to each, as required by law.  
I commence 10.44 chs. East of the  $\frac{1}{16}$  sec. cor. on  
the west boundary of the S.W.  $\frac{1}{4}$  of sec. 29 in T<sub>p</sub>.  
6 N. R. 35 E. W. 7<sub>m</sub>.

Set saved fir post 4x4 ins. - 4 ft. long, 24 ins in  
ground for initial post to Road No 387, marked

R 0 on South face and 387 on North face,  
and raised a mound of earth 4  $\frac{1}{2}$  ft. base and  
2 ft high around post, against fence on North  
side of lane course E + W.

Thence I run var 21° 00' E

also S 8° 00' W along center of Road in lane.

8.75 Irrigating ditch 4 lks. wide runs west.

10.00 J. W. Hodgen's house bears west about 250 lks.

10.75 Spring Creek swamp + water 50 lks wide runs N. W.

19.80 Intersect line bet. Secs. 29 + 32; set angle post  
and turn west along section line.

27.95 The cor. to secs. 29-30-31-32

Set angle post no. 2. and turn  
South along line bet secs. 31+32. Ascend

32.00 Summit

61.50 Descend

64.50 Ravine, course N.W.

67.24 The  $\frac{1}{4}$  sec. cor. bet secs. 31+32.

Int a road bearing NE+SW

I set a sawed post 4x4 ins. 4 ft. long - 2 $\frac{1}{2}$  ins  
in ground for terminus, marked R on N  
face and 387 on S. face; raised a mound of  
earth 4 $\frac{1}{2}$  ft. base and 2 ft. high around the  
post, which is set 45 links S of said  $\frac{1}{4}$   
sec. cor. against a fence bearing E+W.

I hereby certify that the foregoing are the  
correct field notes of Road Survey no. 387 for  
Umatilla County, Oregon.

Jno. C. Arnold, County Surveyor

Field Notes  
Road No 387

Filed April 26. 1892.

W. M. Greer  
Clerk