

Field Notes of Road Survey No 401 for Umatilla County, Oregon.

I meet H. L. Frazier, Geo. DeStaven and A. M. Elam viewers on road survey No. 401, for Umatilla County, Oregon, at Milton August 29th 1892, and duly administer oath to each as required by law. H. M. Ritner and J. C. Still called to chain and mark, each of whom, duly qualified.

Under direction of said viewers, I find a point 20.17 ch South of $\frac{1}{4}$ sec. cor. bet. secs. 26 & 35, T. 6 N. R. 35 E. W. M., purporting to be the $\frac{1}{16}$ sec. cor. on the W. body. of the N.E. $\frac{1}{4}$ of said Sec. 35. This point is in the center of a traveled road in lane, 62 links wide, course N. & S., called the lower or west Walla Walla & Milton wagon road; fences run E. & W. from points on opposite sides of the said lane, and a road notice has been posted on the E. side of said lane, at this point;

I set regulation initial post, against fence on E side of lane, 43 lks. N.E. of initial point, as described, and run thence, along fence - Va. N. 21 E.

East

^{chs.}
13.20 Creek 15 lks. wide, runs N. W.

19.45 Fence course N. & S.

22.60 Creek 20 lks. wide, course N. W.

39.04 Stone cor., purporting to be $\frac{1}{16}$ sec. cor.

55.50 Road bears N. & S.

58.47 Hub in center of plowed furrows, course E. & W. and 30 lks. dist. both N. & S. from said hub, which has a tack in top, and, from which, on opposite sides of the said furrows, there is a plowed furrow, course N. & S.

58.87 A point in center of space included between said parallel furrows running E. & W. 60 lks. dist from each other and similar parallel furrows running N. & S. 90 lks. dist. from each other. At this point there is a post in stone mound, on which post a road notice has been posted. I set terminus 45 links S.W. of said center point in angle made by said furrows. All the posts are of the size, and are marked and set in mounds, as required by law.

I hereby certify that the foregoing are the original and correct notes of Road Survey No. 401, for Umatilla County, Oregon.

Jno. C. Arnold, Surveyor.