

ROAD NO

402

Road 402

In the matter of Viewing Surveying and laying out
 County Road 402
 Commencing at the North East corner of the North
 west Quarter of Sec 31 Township 4 North Range 37 East
 of W.M. Thunes East one mile to the North East corner
 of the North West Quarter of Sec 32 Township 4 North Range
 37 East of W.M. Said road to be sixty feet wide
 So the Honorable County Court of the State of Oregon
 for Umatilla County.

We the undersigned the Viewers heretofore appointed to view
 and locate Road No 402 submit the following report.

Pursuant to an order of the Honorable Court we met Geo.
 C. Arnold County Surveyor at Res of S. J. Phillips on the
 20th day of Oct. 1892 and were by him duly sworn to
 faithfully and impartially discharge the duties of our
 appointments, we called to our aid S. J. Phillips, H. M. Rittner
 Chainman, Marker, who were by the surveyor each duly
 sworn, we viewed, surveyed and located said Road No
 402 as specified in our order, we find the route
 practicable, and shorter than the road now travels,
 (not a County road) and of much use to the General Public
 we would therefore recommend that said Road no. 402,
 be declared a public highway.

Witness our respective hands this 27th day of Oct
 A. D. 1892.

H. Gans }
 S. J. Phillips } Viewers, Road Survey No. 402
 W. A. Clark }

Filed Nov 9, 1892 }
 W. M. Pierce }
 Clerk }

Field notes of
 must have
 on road see
 J. Phillips
 we call Sa
 who likewise
 said Viewers
 E. for ini
 tial post
 35° E. 37 ft
 ascending
 400
 750
 2250
 2636
 3200
 3940
 3985
 4215
 4710
 5270

Field Notes of Road Survey No. 402 for Umatilla Co. Oregon.

I must have seen Sam J. Phillips and Wm A. Clark Viewers on road survey No 402 for Umatilla Co. Or. at Rio of Saml J. Phillips Oct 26. 1892 and Qualify each according to law we call Saml J. Phillips and H. M. Ritter to Chain and mark who likewise Qualify, after which under the direction of said Viewers, I find the 14 Sec. Cor. bet Secs 30 + 31 T. 4 NR 37 E. for initial point in Road Survey No 402 and set initial post sawed fir 4x4x4 mks 0 on S, and R 402 on E. S. 35° E. 37 ft dist. From said initial point I run East Va. 21° ascending gently through brush and timber,

- 400' Summit + 425' Descent + 705' Old Road N.W. + S.E.
- 750' Swag. Course N. + 1200' Ravine, course N. ascend gently
- 2250' Summit level brush + 2400' ascent.
- 2636' Cor. to Secs 29-30-31-32 on N. hill side, on line.
- 3200' Close for the day Oct 26th 1892.
- 3940' Int N+S line about 75 ft S of spruce 10 ins dia, blzd, N.W. S.W. + N.W. I cut into N.E. blzd and find mks 2x9
- 3985' I cut 3985 on S side of fir 12 ins. dia, on line, notched
- 4215' Old road bears N.E. + S.W.
- 4710' Int. traveled road, Course N.E. + S.W.
- 5270' Int N+S line 22 feet South of 14 sec. cor. bet. Secs 29 + 32, which I find in need of repairing. I set stone and make new bracing trees, as per notes on file in my office, and cut R. 402 on W. side of S.W. bracing tree, for terminal post in road survey No 402 The initial post was set in an earth mound 4 ft. sq. at base and 2 ft high. Oct 27th. 1892.

I hereby certify that the foregoing notes of Road Survey No. 402 for Umatilla Co, Oregon, are correct.

Jno. C. Arnold.
County Surveyor.

Filed Nov 9-1892
W. M. Pierce }
Clark }

out
north
57 East
est corner
North Range
Dragon
to View
ort.
met Jno.
on the
vorn to
es of our
H. M. Ritter
ach duly
Road No
out
olds,
nal Public
no. 402,

Oct

Plat of Road Survey No 402

Township 4 N Range 37 E. W. M.

I hereby certify that the following plat of Road Survey No 402 for Wasilla County Oregon is correct.
Jno. C. Arnold, Surveyor.

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
Road Initial 29 30 31 32 33 34 35 36 Road Road 402 Terminus 28 27 26 25					

Filed Nov 9-1892

W. M. Pierce
Clerk

9349