

Field Notes of Road # 533 $\frac{1}{2}$

In accordance with an order issued by the Honorable County Court of Unistilla County I met on April 16th Wm. Sigman, J. E. Walden and W. H. Beathe at School House # 49 as specified, and after duly qualifying, we proceeded to the initial point of Road # 533 $\frac{1}{2}$  and proceeded to locate and survey said Road. We called to our aid J. B. Stark and F. Beathe, to act as chainmen and they were duly qualified. I planted post as per instructions 30' E of initial point marked R 533 $\frac{1}{2}$ .

Standard Time	10° 30' A.M.
Local " "	10 24 " "
Declination of Sun	10° 03' 45'
Altitude angle	53°
Latitude	45° 42'
Variation of Needle	20° 30'



Field Notes of Road #533

Beginning at a point the 1/4 Sec Cor. on E line of Sec 27. T4N R36E

	Dist	L	R	T. D.
South	924'	26°47'		
S. 26°47'E	198'		58°53'	
S 32°06' W	354'	To intersection with County Road at which pt. 30 East I set post as per instructions.		

I hereby certify that the foregoing  
is a true and correct copy of  
notes of survey of Road 533  
as made by me  
E. W. Macomber  
County Surveyor.

Road 533 1/2

Filed May 9, 1902

W. H. Chamberlain

Clerk

By: B. B. Hall

Deputy