

IN THE BOARD OF COUNTY COMMISSIONERS OF UMATILLA COUNTY

STATE OF OREGON

IN THE MATTER OF LEGALIZATION)
OF WHITE RESERVOIR ROAD,)
COUNTY ROAD NO. 713)

RECEIVED

AUG 20 2003

ORDER NO. RD2003-25

UMATILLA COUNTY RECORDS

WHEREAS, the Umatilla County Board of Commissioners may, under authority of ORS 368.201 to 368.221, order a county road that has been used and traveled by the public for ten (10) years or more to be surveyed and recorded, and

WHEREAS, the Umatilla County Board of Commissioners ordered the survey of White Reservoir Road (County Road #713), the midpoint of which is located approximately 5 miles northwest of Umapine in Umatilla County, Oregon, and lies in Sections 17, 18, 19, and 30, Township 6 North, Range 34 E.W.M, and

WHEREAS, the Notice of Hearing was posted and all owners of abutting property affected by the legalization procedure were served copies of the Notice of Hearing, and

WHEREAS, the Umatilla County Board of Commissioners on August 20, 2003, held a public hearing and finding that it would be in the public interest to legalize the road:

THEREFORE IT IS NOW ORDERED that the road be legalized as follows:

A 60-foot wide strip of land for road and utility installation purposes located in Sections 17, 18, 19, and 30, Township 6 North, Range 34 East of the Willamette Meridian, the centerline of which is more particularly described as follows:

Commencing at a brass-capped monument marking the closing corner common to Sections 17 and 18, Township 6 North, Range 34 E.W.M. on the Oregon-Washington State Line as it is currently monumented; thence N89°59'30"E, 224.67 feet to a point on said Oregon-Washington State Line and the true point of beginning of this description; thence S01°03'47"W, 2281.69 feet; thence S00°21'22"W, 317.59 feet; thence 301.52 feet along an 899.48-foot radius curve right (the long chord bears S09°57'34"W, 300.11 feet); thence S19°33'45"W, 239.94 feet; thence 199.67 feet along a 1343.37-foot radius curve right (the long chord bears S23°49'14"W, 199.49 feet); thence S28°04'44"W, 101.72 feet; thence 550.43 feet along a 763.41-foot radius curve left (the long chord bears S07°25'23"W, 538.59 feet); thence S13°13'57"E, 242.84 feet; thence 152.16 feet along a 720.92-foot radius curve right (the long chord bears S07°11'10"E, 151.88 feet); thence S01°08'22"E, 347.78 feet; thence 198.01 feet along a 2830.59-foot radius curve left (the long chord bears S03°08'39"E, 197.97 feet); thence S05°08'53"E, 260.67 feet; thence 253.68 feet along a 723.58-foot radius curve right (the long chord bears S04°53'44"W, 252.38 feet); thence S14°56'21"W, 1247.96 feet; thence 127.67 feet along a 1539.19-foot radius curve right (the long chord bears S17°18'56"W, 127.63 feet); thence S19°41'31"E, 1490.46 feet; thence S20°14'44"W, 459.81 feet; thence S18°42'30"W, 840.35 feet; thence S17°51'11"W, 621.61 feet; thence 374.45 feet along a 966.63-foot radius curve left (the long chord bears S06°45'21"W, 372.11 feet, said point being the terminus of this description and bearing S45°58'20"E, 1218.22 feet from a

Original to: Commissioner's Journal
Copy to: Doug Olsen, County Counsel



2003-4450518 2 of 2

Order No. RD2003-25 Page 2

brass-capped monument marking the North 1/4 Corner of Section 30, Township 6 North, Range 34 E.W.M. EXCEPTING THEREFROM that portion lying within the right-of-way limits of County Road No. 700, Stateline Road, and any portion lying within the State of Washington.

Bearings and distances are NAD '83('91) grid. The plat of the above described road is recorded as Survey No. 03-131-C in the Umatilla County Surveyor's Office.

Dated this 20th day of August, 2003

UMATILLA COUNTY BOARD OF COMMISSIONERS

ABSENT

William S. Hansell, Chairman


Emile M. Holeman
Emile M. Holeman, Commissioner

Dennis D. Doherty
Dennis D. Doherty, Commissioner



ATTEST: OFFICE OF COUNTY RECORDS

By: Jean Hemphill
Records Officer



APPROVED AS TO FORM:

Doug Olsen
Doug Olsen, County Counsel

State of Oregon)
County of Umatilla)

This instrument was received and recorded on
08-20-03 at 2:10

in the record of instrument code type DE-ORDER

Instrument Number 2003-4450518
Fee 0.00

Office of County Records
Jean Hemphill
Records Officer