

FIELD NOTES

County Road No. 865

Market Road No. 29

Date July, 1925

Adams - Spring Hollow.

STATION	Curve Data	Length of Tangents and Curves Fe.	Bearing	REMARKS
0+00 P.C.	31° C.R. Δ=23°02'	74.3	N. 89°30' E.	Beginning of project, which point is 28.6 ft North and 792.0 East of the one-fourth section corner common to sections 3 and 4, T. 3N., R. 34 E. W.M.
0+74.3 P.R.C.	31° C.L. Δ=23°02'	74.3	S. 67°28' E.	Equation
1+48.6 P.T. = 0+37.6 P.O.T. =		1149.0	N. 89°30' E.	Equation
11+86.6 P.Q.T. Back = 10+00.0 P.O.T. Ahead =		455.0	N. 89°30' E.	Which point is coincident with the center of section 3.
14+55.0 P.O.T.		2015.5	N. 89°30' E.	
34+70.5 P.C.	4° C.R. Δ=33°15'	831.2		
43+01.7 P.T.		935.2	S. 57°15' E.	
52+36.9 P.C.	4° C.R. Δ=17°10'	429.2		
56+66.1 P.T.		965.7	S. 40°05' E.	
66+31.8 P.O.T. = 66+26.2 P.C. =	8° C.L. Δ=14°20'	179.2		
68+05.4 P.T.		193.0	S. 54°25' E.	
69+98.4 P.C.	6° C.R. Δ=16°31'	275.3		
72+73.7 P.T.		200.1	S. 37°54' E.	
74+73.8 P.C.	4° C.L. Δ=18°58'	474.2		
79+48.0 P.T.		132.5	S. 56°52' E.	
80+80.5 P.C.	4° C.R. Δ=10°22'	259.2		
83+39.7 P.T.		458.2	S. 46°30' E.	
87+97.9 P.C.	4° C.L. Δ=8°54'	222.5		
90+20.4 P.T.		494.8	S. 55°24' E.	
95+15.2 P.C.	6° C.L. Δ=16°53'	281.4		
97+96.6 P.T.		20.6	S. 72°17' E.	
98+17.2 P.C.	7° C.R. Δ=12°31'	178.8		
99+96.0 P.T.		505.4	S. 59°46' E.	
105+01.4 P.C.				

FIELD NOTES

County Road No. 865

Market Road No. 29

Date July 1925

Adams Spring Hollow.

STATION	Curve Data	Length of Tangents and Curves	Bearing	REMARKS
105+01.4 P.C.	3° C.L. Δ = 6° 17'	209.4		
107+10.8 P.T.		127.0	S. 66° 03' E.	
108+37.8 P.C.	6° C.R. Δ = 28° 21'	472.5		
113+10.3 P.T.		1399.8	S. 37° 42' E.	
127+10.1 P.C.	2° C.R. Δ = 7° 35'	379.2		
130+89.3 P.T.		198.2	S. 30° 07' E.	
132+87.5 P.C.	4° C.L. Δ = 22° 33'	563.8		
138+51.3 P.T.		122.3	S. 52° 40' E.	
139+73.6 P.C.	8° C.R. Δ = 27° 41'	346.0		
143+19.6 P.T. = 143+06.0 P.O.T. =		854.0	S. 24° 59' E.	
151+60.0 P.C.	2° C.L. Δ = 8° 28'	423.3		
155+83.3 P.T.		1005.7	S. 33° 27' E.	
165+89.0 P.C.	1° C.L. Δ = 11° 42'	1170.0		
177+59.0 P.T.		1093.0	S. 45° 09' E.	
188+52.0 P.O.T.		61.2	S. 45° 09' E.	Which point is 703 ft West of the one fourth corner common to sections 13, T.3 N., R. 34 E. W.M. and 18, T.3 N., R. 35 E. W.M.
189+13.2 P.C.	4° C.R. Δ = 6° 56'	173.3		
190+86.5 P.T.		901.3	S. 38° 31' E.	
199+87.8 P.O.T.				End of project, which point is 875.0 ft. South of the one-fourth section corner common to sections 13, T.3 N., R. 34 E. W.M. and 18, T.3 N., R. 35 E. W.M. Said point is coincident with station 321+64.0 of the Adams-Thorn-Hollow Market Road No. 35.