

ROAD NO

272.

Road No 272

Report of Viewers. Field Notes ^{and} Plat of Survey of a County Road, commencing at School House on Decline bet Secs 20 & 21 T. 4 N. R. 32 E. intersecting South Cold Spring County Road at a point where said Decline intersect County Road

Report of Viewers

To the Hon County Court for Umatilla County, Oregon:

We, the undersigned, viewers on a County road prayed for by Robert Rainey ^{and} others would most respectfully recommend that the petition for said road be granted, This road is in our opinion much needed; it connects the road down the South Fork of Cold Spring Cañon, with the road down the Middle Fork of the same, thereby giving the people in the vicinity an outlet Southward to the County seat ^{and} to the Blue mountains. The route is very practicable ^{and} the road can be built ^{and} kept in repair at small expense,

Most respectfully

L. M. Figg }
L. Knowlton } Viewers
D. C. Cargill }

Field Notes of the survey of County Road No. 272

Under the direction of L. M. Figg, L. Knowlton ^{and} D. Cargill, whom I met, August 18th 1886 as viewers, I called Frank Cargill ^{and} Adolph Eggerth as chainbearers ^{and} Robt Lang as marker ^{and} forthwith proceed with Road Survey No. 272-

I commence at intersection of Middle Cold Spring Road with line bet Secs 20 & 21 T. 4 N. R. 32 E. Set initial post marked R on south side, in mound from which the 6" mile post on said Cold Spring road bears N. E. 12. 34 chs ^{and} Cole's School House bears N. W. 1. 08 chs. - I run South on true line bet Secs, 20 & 21 T. 4 N. R. 32 E.

69.00 Cor. for Secs, 20, 21, 28 & 29; I continue South on true line bet Secs 28 & 29

80.00 Set 1 mile post about 43 links west of line

20.50 The 1/4 Sec. cor. bet. Secs 28 & 29

69.94 Cor. for Secs 28, 29, 32 & 33, I continue South on true line bet Secs 32 & 33.

80.00 Set 2 mile post about 40 links west of line

30.32 The 1/4 Sec. cor. bet. Secs 32 & 33

60.75 Intersect South Cold Spring Road. Set post on line - marked R on north side.

All the posts are of the size ^{and} are marked ^{and} set in earth mounds as required by law -

Jno. C. Arnold

County Surveyor

Umatilla Co. Or.

Plat of Road No. 272.

Township 4 N. Range 32 E

8	9
17	16
20	21
29	28
32	33

not sold before
initial
road

1 mile

2 mile

Sanimo
Spring
Wagon Road

Book 9. page 350

" 9 " 402

I hereby certify this to be a true plat
of Road Survey No. 272

Jno B. Arnoes
Surveyor

Recorded Oct 22 " 1886

G A Hartman

County Clerk