

Field Notes of Survey of Road # 527. Made July 23, 1901.
 Beginning at a Stone the 1/4 Section Corner between Sections 17 and 18.
 Township 5 South Range 32. E.W.M. at which point I take an
 observation on the sun to establish true North.

Standard time 1 o'clock P.M.
 Local time 1.04^m 30^s P.M.
 Latitude 45° 09' N
 Declination of sun 20° 06' 15" N
 Refraction 0° 00' 34"
 Altitude angle 62° 00'
 Variation 19° 45' E.

20 feet south of beginning I set required post marked R. 527.
 Thence I Run

	Left	Right			
7789'45" E.			5269.	5269.	1/4 sec cor. E line sec 16.
North	89°45'		11	5280.	set 1 mile Post.
			2736		Cor to sec. 8, 9, 16 and 17.
East		90°	2544	5280	set 2 mile Post
			2740		Cor to sec. 9, 10, 15 and 16.

at this point I intersect County Road and set post marked R.
 J. 527. 20 feet to south to mark terminus of Road as per
 instructions

I hereby certify that the foregoing is a true and correct copy
 of the field notes of Survey of Road # 527. as made by me
 July 23, 1901

E. E. Macomber
 County Surveyor

ROAD No
 Public Easement
 Rd #531

Field Notes of Road #
 This Road being one of public easement no viewers were
 appointed. = Survey made Aug 29, 1901.

Road as yet has received no number. therefore initial point
 not marked with number at the time of survey.

Beginning at the (1/4) Corner between Sections (1) one
 and (12) Twelve in Township (1) one South Range (32)
 Thirty-two. E.W.M. at which point I took an observation
 on the sun to establish true North.

Standard time 11 o'clock A.M.
 Local time 11^h 04^m 30^s A.M.
 Latitude 45° 30' North
 Declination 9° 24' 24"
 Refraction 0° 00' 44"
 Altitude angle 53° 00'

Variations of Merid. $19^{\circ} 30' E.$

Rd #533

Thence, I go on Section line between Sections 1 (one) and (12) Jeweler Townships (1) one South Range, 32, thirty two E, W, M.

Chairman A. D. Sloan

C. E. Macomber.

Course	Left	Right	Distance	Total Distance	Remarks
$N. 89^{\circ} 26' W.$			427.	427	
$N. 80^{\circ} 03'$		$9^{\circ} 23'$	215	642.	To west bank of Small creek bridge 15'.
$S. 72^{\circ} 07' W.$	$27^{\circ} 50'$		114.	756.	
$S 37^{\circ} 23' W$	$34^{\circ} 44'$		350	1106	
$N 5^{\circ} 45' W.$		$136^{\circ} 52'$	400	1506	
$S 57^{\circ} 45' W.$	$122^{\circ} 30'$		169.	1675.	
$N 89^{\circ} 26' W$		$38^{\circ} 49'$	1336.	4011.	Center of Co Road * 438.

No Number given Road, at terminus of Survey

I hereby certify that the foregoing is a true copy of Field Notes as recorded, by me, in above survey C. E. Macomber County Surveyor.

Filed Sept 3rd 1901

W. O. Chamberlain Clerk.

By B. B. Hall, Deputy.

ROAD No

533.

In the matter of viewing, surveying and laying out county road No 533 to the Honorable County Court, of the State of Oregon, for Umatilla County:

We the undersigned, Viewers heretofore appointed to view and locate Road no 533 submit the following report: Pursuant to an order of the Honorable Court we met C. E. Macomber Surveyor, at Adams on Dec. 20, 1901 and were by him, each, duly sworn to faithfully and impartially discharge the duties of our appointments.

We called to our aid W^m Kilgore }
 Chas S Marsh } Chairmen.
 C. E. Macomber. Marker.

who were by the Surveyor, each, duly sworn. We viewed, surveyed and located said Road No. 533, as specified in our order and find that this road is a necessity to the general public and we respectfully recommend that petition for same be granted.

Charles S. Marsh }
 Geo M Barister } Viewers, Road Survey No 533
 Wm Kilgore