

FIELD NOTES OF COUNTY ROAD NO. 752.

I commence at the S. W. corner of the N. W. $1/4$ of section 33 T. 5 N., R. 29 E., W. M. At a point 20 ft. north and 20 ft. east of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 752: dug pits 18 X 18 X 12 ins., N. & E. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post; *Thence following subdivisional section line east 5.55 chains irrigation ditch 4 lks. wide.*
Thence east 80.53 chains to the S. E. corner of the N. E. $1/4$ of said section 33 in said township and range, a point from which I set 20 ft. north and 20 ft. west, a post 4 ft. long, 4 ins. square, marked R. T. 752: dug pits 18 X 18 X 12 ins. north and west of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County road No. 752 are correct, according to survey made by me on the 2nd day of June. 1913.

Geary Kimbrell
Surveyor for Umatilla County Oregon.