

pp. 33

Field Notes of County Road No. 729

I commence at the 1/4 section corner between Secs. 24 & 25 T. 5 N. R. 28 E., W. M. At a point 20 ft. E. and 20 ft. N. from aforesaid corner, I set a post, 4 ft. long, 4 ins. square, marked R. 729; dug pits, 18 X 18 X 12 ins., E. & S. of post, and raised mound of earth, 18 ins. high 4 ft. base around post.

Thence following the subdivisional section line south 5.40 chs. to irrigation ditch, course S. W. 31.30 chs. to pipe line, course N. E. 80.00 chs. to a point from which I set, to the left, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M; dug pits, 18 X 18 X 12 ins., E. and W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence continuing on subdivisional section line south 89.40 chs. to irrigation ditch 8 lks. wide course S. E. 159.30 chs. to the S. W. corner of the S. E. 1/4 of section 36 in said township and range from which I set, 20 ft. south and 20 ft. east a post, 4 ft. long, 4 ins. square, marked R. T. 729; dug pits N. and south of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County Road No. 729 are correct as surveyed by me on the 27th day of Oct. 1911.

Geary Kimbrell
Surveyor for Umatilla County, Oregon.