

4  
3

FIELD NOTES OF COUNTY ROAD NO. 706

I commence at a point 227 ft. N. of the S. W. corner of the N. W. <sup>of the N.W. 1/4</sup> 1/4 of Sec. 3, T. 4 N., R. 28 E., W.M. At a point 33 ft. W. of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 706: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post. Thence N. 56° 5' E. 262 lks. O. R. and N. Co's railway track; 459 lks. to a point 30 ft. east of the east line of the O. R. and N. Co's. right of way, to Angle 1. Thence N. 33° 55' W. 17.91 chs. to a point due south of the S. W. corner of the S. E. 1/4 of the S. E. 1/4 of Sec. 33 T. 5 N., R. 28 E., W. M. Angle 2. Thence north 1.96 chs. to the said S. W. corner of the said S. E. 1/4 of the S. E. 1/4 of Sec. 33. Thence following the subdivisional section line north 20.13 chs. to the N. W. corner of the S. W. 1/4 of the S. W. 1/4 of said Sec. 33 Angle 3. Thence N. 18° 45' W. 36.41 chs. to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

61.20 chs. to the 1/4 Sec. corner between Sec's. 28 & 33 in said township and range. Angle 4. Thence north 55.11 chs. to a point from which I set, to the left, 30 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

79.84 chs. to the 1/4 Sec. corner between Secs. 21 & 28

in said township and range from which I set, 30 ft. S., &  
30 ft. W., a post, 4 ft. long, 4 ins. square, marked R.  
T. 706: dug pits S. & W. of post, and raised mound of earth,  
18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes  
of County road No. 706 are correct as surveyed by me on  
the 20<sup>th</sup> day of May 1911.

Geary Kimbrell

Surveyor for Umatilla County, Oregon.