

## Field Notes of Road No. 506

I met J. M. Ferguson Thos. Thompson and C. A. Traiger Viewers at the Beginning of Road No. 506 on the 22<sup>nd</sup> day of March 1899 at 10 o'clock A.M. Commencing at yard gate near residence of J. W. Gillilan a point in Lot 2 Sec 8 T2N R32E WMC about 50 feet west and 400 feet north of a point on West Boundary of the W C McKay Donation Claim No 38 said point being 380 lks North and 15.50 chains East of Center said 8 set stake at initial point at East gate Post marked R. 506 Built mound around Post and dug pits East and West of Post

thence I run S 1° 35' W	4.35 chains		287.58
"	S 28° E 1.87	" to compromise line	123.42'
"	S 83° 35' E $\frac{6.55}{6.30}$	" to West Body McKay Donation Claim	
"	S 83° 35' E 5.50	"	399.30'
"	S 65° 30' E 4.29	"	283.14'
"	S 89° E 7.10	"	468.60'
"	S 65° 30' E 3.50	"	231.00'
"	S 68° E 4.35	"	287.10'
"	S 59° E $\frac{19.28}{44.02}$	" to East Body McKay Donation Claim which is also West Boundary of Mrs Kines Land	
thence S 61° E	11.04 chains		
"	S 65° 30' E 4.68	"	
"	S 65° E $\frac{14.35}{30.03}$	" to line bet. Kine & Bailey	
thence S 64° 35' E	16.50 chains		
"	S 38° E $\frac{7.05}{23.58}$	" to South East cor of J. H. Bailey Land	
thence East	14.09 chains	to County Road leading	



from Pendleton to Pilot-Rock which is  
 also Beginning of County Road No 430 and  
 at a Point between Lot 8 Sec 9 and Sec 16 a  
 distance of 445 1/2 feet West of the S E corner  
 of Lot 8 Sec 9 in S 2 N 63 2 E W 1/4  
 Set Stake at Terminus from which a fence post  
 in Walkers fence bears S 50° E 48.160 distant  
 which I mark B T 506 dug pits South and East  
 and built mound around post.

I hereby certify that the foregoing are correct  
 Field notes of Road No 506 as surveyed by me  
 on the 22<sup>nd</sup> day of March 1899

assisted by Chas. A. Frazier and J. M. Ferguson  
 as Chairman and Thos. Thompson Hayman.

John W. Kimbrell Surveyor  
 for Umatilla County Oregon

I hereby certify that the foregoing are a correct copy of  
 Field notes of Road No 506 as surveyed by me on the  
 22<sup>nd</sup> day of March 1899 John W. Kimbrell County Surveyor