

ROAD NO  
473.

In the matter of viewing, surveying and laying out County Road No 473  
To the Honorable County Court of the State of Oregon for Unadilla County.

We, the undersigned, the Jurors heretofore appointed to view and locate Road No 473, submit the following report. Pursuant to an order of the Honorable Court we met John W Kimball Surveyor, at Ukiah Oregon, on the 5th day of February 1896 and were by him, each duly sworn to faithfully and impartially discharge the duties of our appointments. We called to our aid Geo. Vinson, C. Bolus, Chaimen, E B Gamber, Marked, who were by the Surveyor, each, duly sworn. We viewed, surveyed and located said Road No 473 as specified in an order and find the Route practicable and would most respectfully recommend the same to be declared a Public Highway.

J. W. M. Reynolds

Filed Feb 28 1896

C. A. M. Reynolds

Viewers, Road Survey No 473

B. S. Burroughs, Clerk

Jacob Barw

Field notes of Road Survey No 473.

I commenced at the center of the south 1/2 Sec. 14, in Township 5 South of Range 31 East W.M. At post 4x4 inches and 4 feet long marked R No 473. 20 feet south of the initial point, dug pits East and West of post and built mound of earth 4 feet wide at base and 18 inches high around post.

Thence	Chain	Distance	
S 87° W	207		A 1
S 73° W	5.66	7.68	2
N 637° W	2.40	10.08	3
N 7614° E	13.42	23.50	set post 4x4 inches and 4 feet long

40 feet West of Road terminus which is in the center of the south end of Camas street in the Town of Ukiah, in Unadilla County Oregon. I marked the post R. J. No 473 on East face and dug pits North and West of post and built mound 4 feet wide at base and 18 inches high around post also commencing at angle 2 on the above described road, I set post 4x4 inches and 4 feet long, 20 feet South and 20 feet East of angle No 2 marked R No 473 dug pits East and South and built mound 4 feet wide at base and 18 inches high around post

Thence	Chain	Distance	
S 7° 30' W	10.06		
S 17° W	6.06	16.12	
S 35° W	12.40	28.52	to center of County road

from which I mark a Pine Tree 6 inches diameter bears. W. 71° W 79.26 distant marked R. J. No. 473

I hereby certify that the above field notes are correct to the best of my belief

John W. Kimball  
County Surveyor.

This the 5th day of February 1896  
Filed February 28. 1896  
B. S. Burroughs  
Clerk

