



NARRATIVE: The purpose of this survey is to determine why there is more area in possession of L. Enos than what the County tax roles show. The County tax map says that the Enos parcel contains 0.44 Acre (B. 239, P. 22). My survey of the land in possession computes at over 1.3 Acres.

The point of beginning of most of the descriptions in this area is a point on the northerly R/W line of U.S. Hwy #730 a certain distance easterly of the intersection of said R/W line with the southerly R/W line of the U.P.R.R. Said point is said to be marked by an Iron Pin. I retraced the location of the center of the OLD Highway using a R/W map (38-19-2) dated 1921 using the center of the concrete Arch Bridge as a base. I intersected the northerly R/W line (30') with the southerly R/W line (50') of the U.P.R.R. and searched for the above mentioned Iron pin with no results. The relocated Hwy R/W map shows that the R.R. R/W could decrease to 30' or 40'. I also searched for the Iron pin at those locations with no results.

Since it is not clear where the point of intersection of the R/W's was and since the fence between Osterkamp & Enos has been there for over 20 years (according to Lorraine Enos), I surveyed that fence to describe its location.

84-015-A

**SURVEY FOR LORRAINE ENOS
IN THE NE 1/4 Sec. 18, T5N, R28E, WM.
UMATILLA COUNTY, OREGON**

3/3/84 (000) of record Job # 58402023
0 1/2" x 24" Iron rod set with Alum. tag. stamped 951

EDWARDS SURVEYING R.O. Box 763
567-3336 HERMISTON, OREGON

ENOS BC. 50.9' South of
C/A Sec. 18. I Believe
set by W. Harris Co.
in late 60's or early 70's

OLD HWY
6° C.R.
(A 11° 22')
ST 95.0
L 189.4

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 18, 1871
G. DENNIS EDWARDS
951