



Curve Data

- $r = 290.00$
 $a = 95.81$
 $t = 48.35$
 $ch = 95.38$
 $N 72^{\circ} 44' 11'' W$
- $r = 242.43$
 $a = 48.68$
 $t = 24.37$
 $ch = 48.50$
 $N 69^{\circ} 00' 44'' W$
- $r = 242.43$
 $a = 218.91$
 $t = 117.55$
 $ch = 211.54$
 $S 79^{\circ} 22' 40'' W$

NARRATIVE:

The purpose of this survey was to locate the boundaries of that property belonging to Rodney and Doris Giles as described on Roll 96, Page 1964 of the Umatilla County Deed Records.

The West line of this property is described as the East line of that property belonging to Walter and Lucille Onstot, Book 221, Page 240 of the Umatilla County Deed Records.

The West line of the Onstot property is the West line of the Northeast one-quarter of the Northeast one-quarter of Section 33, T.4N., R.38E., W.M.. To establish this line we used the Brass Cap at the E_{1/4} ²⁸/₃₃ to the North and the best evidence to the South was a blaze line which ran South from Skyline Road. Several of these trees had barbed wire grown 6 to 8 inches into the tree.

Bearings were based on a survey by James Hanley for the U.S. Forest Service in July 1976, Umatilla Co. Survey Dwg. No. L-55-B.

- denotes set $5/8" \times 30"$ iron with aluminum cap stamped PL5 933
- denotes found unmarked Brass Cap set by Hanley
- denotes found BLM Brass Cap

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=200'	Drn. By MLD	Dwg. No. 84-258	Revision 1
	Date 10-5-84	Ckd. By DAM	Job No. 84-124	Revision 2
Survey for ROD GILES		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbein</i> DAVID H. KRUMBEIN		RECEIVED BY Umatilla County Surveyor Date <u>10/84</u> Rec'd By <u>bc</u> No. <u>84-117-A</u>

NE_{1/4}, NE_{1/4}, Sec 33, T4N, R.38E, W.M.

84-117-A