



NARRATIVE:

The purpose of this survey was to locate and monument the corners of that land lying in the NW 1/4 of Sec. 36, T4N, R36E, W.M., owned by Ken Giger and Al Beard for subdivision purposes.

The monuments found and tied or that were set are as noted. Bearings are from this firm's survey for Napier, Umatilla County Surveyor Drawing No. 84-30-B.

The North line of this section was defined in the Napier survey. The Northwest corner and the West 1/4 corner were based on a Wallulis survey by Bill Wells, Umatilla Co. Surveyor No. R-45-C. The East line was surveyed by Streamer in 1976, for Fuessmeyer - Co. No. L-58-B. At the Southwest corner we found a hub in the ground N75°37'27\"/>

A thorough search was made for bearing trees or other evidence of the original corner location including tying to topographical calls. Nothing was found. The hub fits the improvements and proportioned distance to the East and West.

- ⊙ denotes find 2 1/2\"/>
- denotes find 3/4\"/>
- denotes find 3/8\"/>
- denotes find 2\"/>
- ▽ denotes find stone
- ⊠ denotes find Brass Cap, Co. No. R-45-C
- denotes find hub
- denotes set 2 1/2\"/>
- denotes set 3/8\"/>

K KRUMBEIN ENGINEERING LTD ENGINEERS - SURVEYORS - PLANNERS 361 S E Second Pendleton, Oregon	Scale 1"=1000'	Drn By MLD	Drng No. 85-17B	Revision 1
	Date 9-3-85	Ckd By DHK	Job No. 84-05	Revision 2

Boundary Survey for

GIGER & BEARD

NW 1/4, Sec. 36, T4N, R36E, W.M.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 17, 1970
DAVID H. KRUMBEIN
933

RECEIVED BY

Umatilla County Surveyor

1-10-86

CO. NO. 85-164A