



Map of
 J.A. Wight and Agnes Wight Ranch
 located in Secs. 6, T. 2 N., R. 30 E. W.M., and
 Sec. 31 - T. 3 N., R. 30 E. W.M. at
 Nolin, Umatilla County, Oregon.
 Surveyed, staked & platted, June-1955-
 By W. E. O. Criger. -
 Const = 0.92 @ 1" Scale: 1" = 200'

I, W. E. O. Criger, of Pendleton, Oregon,
 do hereby certify that this map was
 made from notes taken during an actual
 survey made by me, on June 28th 1955
 that the monument shown on this map
 is the actual well casing in the well
 which is 8 inches above the top of the ground.
 which is 277 5 ft., north of the south line of
 Sec. 31 - and 15 ft., west of the N-S \pm of said
 Sec. 31.

The No. 2. site shown in sec. 6 is a stake, and
 only indicates the possibility of an alternate
 site.
 W. E. O. Criger.

(Lombard - Apr. 6 - 1955 - U. 805 -)

519-A DRC

W. E. O. CRIGER
CONSULTING ENGINEER

Field Notes for Water Adjudication -

From the South $\frac{1}{4}$ Cor. of Sec. 31-T. 3N., R. 30E.W.M.,
which corner is in place.

I checked the E-W Township line and also
the N-S $\frac{1}{2}$ of Sec. 31

Working from 0.0 Azimuth North, I shot stadia to
the U. P. R. R. R/W East; then followed said R/W-
N. W. and West to an inter-section with the
West $\frac{1}{16}$ Line. Then I continued around the fenced-
in area to the left until it joined the Umatilla
river, then continued around the feed in area
to the left, and also indicated the river S.E. + East
to an inter-section with the N-S $\frac{1}{2}$ of Sec. 6, T. 2N.,
R. 30 E.W.M., thence North on said N-S $\frac{1}{2}$ 1320 ft., to
the N. $\frac{1}{4}$ Cor., thence East on the township line to
the point of beginning. All of which is the
boundaries of the irrigated Area.

The well and pump and well lies 2775 ft., N., and
15 ft., W. of the S. $\frac{1}{4}$ Cor. of Sec. 31.
The No. 2 site shown in Sec. 6 is a stake, and
only indicates the possibility of an alternate site
There was only 1 set-up made and this map
was made in the field and on the site.

W E O Criger -