

646

NW Cor.
Sec. 14
I. PIPE

33'

- 1325.1 -

HIGHLAND AVE.

95.0'

47th ST.

1/16 Cor.
I. PIN

5/8 I. PIN

65.0'

5/8 I. PIN

70.0'

70.0'

65.0'

95'

5/8 I. PIN

5/8 I. PIN

COUNTY ROAD
30' 30'

T4N R28E

SCALE 1" = 40'

DESCRIPTION

Beginning at a point in a line parallel to and 33.0 feet South of the North line of Sec. 14, T 4 N, Range 28 EWM, said point being 95.0 feet West of the East line of NW 1/4 NW 1/4 of said Section 14, and run thence South parallel to the East line of NW 1/4 NW 1/4 of said Sect. 14, a distance of 70.0 feet; thence West parallel to North line said Sect. 14, a distance of 65.0 feet; thence North parallel to the East line of NW 1/4 NW 1/4 said Section 14, a distance of 70.0 feet, to a point in line parallel to and 33.0 feet South of North line of said Section 14; thence East along said parallel line a distance of 65.0 feet to the point of beginning.

Fitted
5/31/49

no repro available

C. H. Storms & Associates

CONSULTING ENGINEERS — ARCHITECTS

304 DENNY BUILDING TELEPHONE 4170 WALLA WALLA, WASH.

- Mechanical
- Structural
- Hydraulic
- Sanitary
- Designs
- Land Surveys
- House Plans
- Blue Prints
- Estimates

A SURVEY FOR

RICHARD GRAHAM

SEC. 14 - T4N - R28 EWM

HERMISTON, OREGON

Date 5-18-49

Drawn By R.B.B.

Checked By G.H.S.

865

SHEET 1 of 1

Q-1314-A4

City Planning
Supervision
Valuation
Surveying
Reports
Designs

C. H. Storms & Associates

CONSULTING ENGINEERS

REGISTERED WASHINGTON, OREGON

C. H. STORMS
Phone 4692-W
G. M. NEWBILL
Phone 2982-M
GEO. LAUBACK
B. F. CHAPMAN
J. O. BICKFORD, Jr.
E. BUCKNER

TELEPHONE 4170
304 Denny Building
WALLA WALLA, WASH.

FILE

FIELD NOTES

OWNER: Richard Graham

TYPE OF SURVEY: Acreage Survey

LOCATION: Section 14, T4N, R28EWM

Beginning at a 5/8" iron pin which marks the NE Corner of the NW $\frac{1}{2}$ NW $\frac{1}{4}$ of Section 14, T4N, R28EWM and also the point of intersection of the centerline of Highland Avenue and the centerline of 4th St. in the City of Hermiston, Oregon, I ran westerly on the North line of said Section 14 a distance of 1325.1 feet to an inch iron pipe which marks the NW Corner of said Section 14. With these two sub-division corners and a 5/8" iron pin marking the SE Corner of the NW $\frac{1}{2}$ NW $\frac{1}{4}$ of said Section 14, I proceeded to make the survey as shown on the accompanying plat.