

Field Notes

Survey of N. W.  $\frac{1}{4}$  of Section 14 TWP. 4 North, Range 28 East.

Pendleton Grain Growers and adjoining Tracts.

Hermiston, Oregon

The purpose of this survey was to establish a mutual agreement line between the Ray Sharp tract and the Pendleton Grain Growers Tract.

This was accomplished by surveying the N, W.  $\frac{1}{4}$  of Section 14 and by establishing the North line of the South Half of the N, W,  $\frac{1}{4}$  of the N. W.  $\frac{1}{4}$  and making that line the common boundary line.

Beginning at the N. W. corner of Section 14, which is a concrete monument. Along the West line of the N. W.  $\frac{1}{4}$ . On a true Bearing of South. 2649.37 West  $\frac{1}{4}$  corner of Section 14. Found 2" Iron Pipe. Along South line of the S. W.  $\frac{1}{4}$ . Bearing South 89°-34' E.

2664.4 Found Hub (established Railroad Engineers) Replaced by  $\frac{3}{4}$  " Iron Pipe.

Along East line of N. W.  $\frac{1}{4}$  on a true bearing of North 0°-- 18' East/  
2643. 18 Found  $\frac{5}{8}$  " Iron Pipe.

Along North Line of N. W.  $\frac{1}{4}$  on a true bearing of North 89°--26'  
West

2650.64 N.W. corner 14

FIELD NOTES

For Survey of Tracts of land in the N.E.  $\frac{1}{4}$  of the N.W.  $\frac{1}{4}$  of  
the N.W.  $\frac{1}{4}$  of Sec. 14, T.4 N., R.28 E., W.M.

Hermiston, Umatilla County, Ore.

By: Verl R. Fraley

Reg. Ore. Land Surveyor No. 183

Found a Conc. Monument which is the N.E. Cor. of the N.E.  $\frac{1}{4}$  of the  
N.W.  $\frac{1}{4}$  of the N.W.  $\frac{1}{4}$  of Sec. 14.

Found a Conc. Monument which is the S.E. corner of the N.E.  $\frac{1}{4}$  of the  
N.W.  $\frac{1}{4}$  OF the N.W.  $\frac{1}{4}$ .

Found also Conc. Monuments opposite to and at rt. angles from the  
P.C. and the P.T. of the  $3^{\circ}$  curve as shown on the accompanying map.

From this data I ran the curve around and checked it and layed out  
and marked with iron pipes the 3 tracts of land as shown.

Q-1354-A4