



NARRATIVE:

This survey was done at the request of the City of Umatilla to survey the boundaries of their property adjacent to, and part of Blocks 2 and 3 of Umatilla Heights, an addition in Umatilla County, Oregon.

We found a 3/4" iron pipe in the center of County Road No. 623 as called for on a survey by Verl F. Fraley, County Surveyor's No. G-766-Ax; using it, the water tank appeared to be off of the City's property. Checking further we found a number of property pins which were set by Cecil H. Storm for the Plat of Umatilla Heights. The location of these pins conflicted with the 3/4" iron pipe found earlier, however since the majority of the property was within the Plat of Umatilla Heights, we used those points to control this survey. Using those pins the tank is well within the boundaries of the property.

There is still some concern over the quarter corner but that will be resolved at a later date by the County Surveyor's Office.

Bearings are based upon the Plat of Umatilla Heights.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes found 3/8" iron pin set by Cecil Storms for Plat of Umatilla Heights
- △ denotes found 3/4" iron pipe 6" below road surface apparently set by Verl Fraley, County Surveyor No. G-766-Ax.

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 50'	Drn. By MCD	Drng. No. 83-49C	Revision 1
	Date 12-1-83	Ckd. By DJK	Job No. 83-121	Revision 2
Survey for CITY OF UMATILLA				RECEIVED BY Umatilla County Surveyor Date 1/5/84 Rec'd By bc No. 84-32-B
SE 1/4, NE 1/4, Sec. 16, T5N, R28E, W.M.				