



NARRATIVE:

The purpose of this survey was to divide out a two acre parcel of land from that property located in the Southeast one quarter of the Northwest one quarter of Section 23, Township 6 North, Range 35 East, W.M. for Carla Latimer.

Bearings are based on a survey by Streamer in 1971 for May Prest, Umatilla County Surveyor Drwg. No. H-8-A.

A survey by C.H. Storms & Associates for Francis Hobson dated June 14, 1951, Umatilla County Surveyor Drwg. No. G-829-A, shows a 1" pin for the North 1/6 C.C. of said Section 23 and a 5/8" pin for the Northwest 1/6, and a rock for the West 1/6 common to Sections 14 and 23. Using this data and Drwg. No. H-8-A which uses common corners, the Northwest 1/4 of the Northwest 1/4 of Section 23 was broken down.

Said property is boarded on the East side by a creek which is shown as it existed on 4-18-84.

- denotes set 5/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes find F/R spike of Drwg. No. H-8-A
- denotes find F/R spike of Drwg. No. S-69-A
- △ denotes find Bolt of Drwg. No. H-8-A
- denotes find stone w/ "x"
- denotes PK nail set

CREEK & DATA

1. 96.01 N17°43'50"E
2. 69.76 N2°23'08"E
3. 33.03 N49°25'54"E
4. 16.89 N6°06'56"E
5. 33.69 N40°11'36"W
6. 83.56 N17°47'10"W
7. 62.02 N12°01'30"E
8. 13.98 N5°09'27"E
9. 47.99 N5°09'27"E
10. 23.82 N33°14'19"W
11. 41.01 N12°26'56"E
12. 46.59 N66°58'46"W
13. 112.70 N22°54'58"W
14. 55.92 S61°43'22"W
15. 48.29 N30°49'46"W
16. 38.99 N54°53'08"W
17. 12.92 N00°E

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=100'	Drn. By MLD	Drng. No. 84-21C	Revision 1
	Date 4-23-84	Ckd. By DMM	Job No. 84-43	Revision 2

Survey for
CARLA LATIMER

David H. Krumbein

RECEIVED BY
Umatilla County Surveyor
Date 5/30/84
Rec'd by *bc*
No. 84-59-B

NW 1/4, Sec. 23, T6N, R35E, W.M.