



- SET 5/8" X 30" REBAR WITH PLASTIC CAP # 951
- ⊙ FOUND 5/8" REBAR WITH ALUM CAP 1987 O.S.H.D. SURVEY BY BATEMAN
- ⊙ FOUND 5/8" REBAR WITH ALUM CAP 1994 O.S.H.D. SURVEY BY SULLIVAN
- ⊙ FOUND 5/8" REBAR WITH PLASTIC CAP #951 ME 1995 SURVEY FOR THE CITY OF HERMISTON.

SURVEYOR'S NARRATIVE:

THE PURPOSE OF THIS SURVEY IS TO SET THE CORNERS OF TWO PARCELS OF LAND IN PREPARATION TO DO TWO PARTITION PLATS. ONE PARCEL BELONGS TO THOMAS N. ABLE #1 JK (R. 188, P. 1659) AND THE OTHER BELONGS TO TOM ABLE JR. (R. 27, P. 263 AND R. 60, P. 1340.)

I SUBDIVIDED THE SECTION AND FOUND THAT THE S 1/16TH SECTIONS 13 AND 14 WHICH I SET IN A 1976 SURVEY FOR THOMPSON IS WITHIN A FEW HUNDRETHS OF ITS TRUE LOCATION SO I HELD IT.

I FOUND THE NE CORNER OF PORTLAND FIXTURES PARCEL WHICH WAS SET BY HERBES IN 1976 FOR STEFANIDES. I STAKED THE NORTH AND EAST LINE OF THAT TRACT BY RETRACING HERBES SURVEY WHICH USED A BRASS CAP AT THE SE CORNER OF SECTION 13 WHICH WAS ABOUT 19 FEET NORTH OF ITS PRESENT POSITION.

1/4 COR FND 2 1/2" BC SET IN CONC. ME 1989 FOR HERMISTON

REGISTERED PROFESSIONAL SURVEYOR

Dennis Edwards
DENNIS EDWARDS
1981

RENEWS 12/31/95

RECEIVED BY
Dennis Edwards Surveyor
Date: 5-95
Rec'd by: [Signature]
No. 95-223B

SURVEY FOR:
THOMAS N. ABLE AND TOM ABLE JR.
LOCATED IN THE S.W. 1/4 OF SECTION 13, TOWNSHIP 4 NORTH, RANGE 28 EAST, OF THE WILLAMETTE MERIDIAN, UMATILLA COUNTY OREGON.

5/08/95 JOB NO. S95003037
EDWARDS SURVEYING P.O. BOX 763
HERMISTON, OREGON 97838 503-567-3336