



SCALE: 1"=400
0 200 400 800

BEARINGS ARE BASED ON SOLAR OBSERVATION, (ALTITUDE METHOD), TAKEN 500 FEET EAST OF THE WEST 1/4 CORNER OF SECTION 10.

NARRATIVE OF SURVEY

THIS SURVEY WAS MADE FOR THE PURPOSE OF MONUMENTING CONTROLLING CORNERS AND POSTING PORTIONS OF THE PROPERTY BOUNDARY BETWEEN ADJACENT OWNERSHIPS IN SECTION 10, TOWNSHIP 1 SOUTH, RANGE 34 EAST, W.M.

THE ORIGINAL SURVEY TO ESTABLISH THE CORNERS OF SECTION 10 WAS PERFORMED BY JAMES F. CURRIN AND JAMES E. NOLAND ON JULY 4 AND JULY 6, 1887. ORIGINAL MARKED ACCESSORY BEARING TREES WERE RECOVERED FOR THE NORTHEAST SECTION CORNER AND EAST QUARTER-SECTION CORNER. THE ORIGINAL MARKED CORNER STONE AND ACCESSORY MOUND OF STONES WAS RECOVERED FOR THE SOUTHEAST CORNER. A PREVIOUSLY BURNED AND DECAYING TREE STUMP WITH EMBEDDED BARBED WIRE AND AN ATTACHED METAL LOCATION SIGN WAS ACCEPTED FOR THE SECTION 9 ACCESSORY BEARING TREE FOR THE WEST QUARTER-SECTION CORNER. THESE RECOVERED CORNER POSITIONS WERE REMONUMENTED WITH STANDARD BRASS CAP MONUMENTS AS NOTED IN THE LEGEND HEREON AND FULLY DESCRIBED IN CORNER MONUMENTATION CERTIFICATES FILED SEPARATELY.

SURVEY MEASUREMENTS WERE MADE WITH A SOKKIA SET 3B I SECOND TOTAL STATION BY A COMBINATION OF CLOSED CONTROL TRAVERSE AND RADIAL TIES. CORNER MONUMENTS TIED AND THE MONUMENT ESTABLISHED BY RADIAL METHODS WERE VERIFIED BY SEPARATE INDEPENDENT OBSERVATIONS.

LEGEND

- SET 2 1/2" BRASS CAP ON 2" GALV IRON PIPE FROM RECOVERED ORIGINAL GLO EVIDENCE.
- SET 5/8" BY 30" IRON PIN WITH 1 1/2" YELLOW PLASTIC CAP MARKED "OR PLS 1634".
- (XOX) GLO DENOTES SURVEY DIMENSIONS BY CURRIN AND NOLAND UNDER SPECIAL INSTRUCTIONS DATED MAY 4, 1887.

REGISTERED PROFESSIONAL LAND SURVEYOR

RECEIVED BY
Umatilla County Surveyor
William L. Hanley
Date 10-95
Rec'd by KK
No. 95-170-13

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639
RENEWS 6/30/97

WILLIAM R. WELLS, PLS 357 N.E. HWY. 11 P.O. BOX 1696 PENDLETON, OR 97801 PHONE: (503) 276-6362		PROJECT: SURVEY FOR: BRIAN SKILLMAN LOCATED IN SECTION 10, T1S., R34E., W.M., UMATILLA COUNTY, OREGON
DATE: 9/18/95	DR. BY: WLH	
CK. BY: WRM	NO: 95-322	

VSkill2A