



FOUND RR SPIKE FROM COUNTY SURVEY Q-0925-C.

Used the record angle from R2.

BASIS OF BEARINGS
 Bearings are based on the north line of the section as per survey 05-001-B.

WEINKE
 Reel 145
 Page 1380

NARRATIVE OF SURVEY

This survey was performed at the request of Mr. Tom Rugg. The purpose of the survey was to identify the location of the deed boundary in relation to the fence and field lines in order to consider allowed uses under the Umatilla County Zoning Ordinances.

No monumentation was requested as part of the survey, however, I remonumented the southeast section corner and south 1/4 corner for the purpose of perpetuating those corner positions. I monumented those points from the evidence as stated on this map. The points are very nearly at the record GLO dimensions and are consistent with the obvious possessory lines throughout the adjoining sections.

The road notes for the county roads at the southeast corner of the section indicate that they went to the original corner point.

The position of the southeast corner of Section 15 as shown on this map is calculated only. I calculated the position using the record angle at the northeast corner of Section 16 and the record length of the east line of Section 16 as shown on survey 96-063-B. I then calculated the inverse between that position and the measured location of the south 1/4 corner as a means to check against the GLO record.

This position calculated from the record data from R2. No field ties were made under this survey.

- LEGEND**
- SET 2 1/4" BRASS CAP ON A 1 1/8" X 30" GALVANIZED IRON PIPE. SEE FILED CORNER CERTIFICATE
 - COMPUTED CORNER POINT ONLY
 - CALCULATED DEED CORNER NOTHING FOUND OR SET
 - FOUND RAILROAD SPIKE. SEE R3 UNLESS OTHERWISE NOTED.
 - {xx} CALCULATED DIMENSIONS ONLY
 - (xx) R1 RECORD DIMENSIONS
 - R1 GLO CONTRACT #107 DATED SEPTEMBER 21, 1864 BY DANIEL CHAPLIN
 - R2 COUNTY SURVEY 96-063-B
 - R3 COUNTY SURVEY 05-001-B
 - R4 ROAD NOTES FOR COUNTY Rd. No. 376
 - R5 ROAD NOTES FOR COUNTY Rd. No. 1069
 - R6 ROAD NOTES FOR COUNTY Rd. No. 1150

REGISTERED PROFESSIONAL LAND SURVEYOR

Stephen K. Haddock

OREGON
 JULY 9, 2004
 STEPHEN K. HADDOCK
 56295LS
 RENEWS 6-30-09

SURVEY FOR
 Mr. Tom Rugg
 P.O. Box 209
 Pilot Rock, OR 97868

LOCATION: E. 1/2, Section 15, T1S, R32E, W.M., Umatilla County, Oregon.

PROJECT DATE: May 12, 2007

Project No. 07-11 SCALE: 1" = 400'

WITNESS TREE SURVEYING
 Stephen K. Haddock, PLS
 P.O. Box 6
 Pilot Rock, Oregon 97868
 (541) 443-2922

RECEIVED BY
 Umatilla County Surveyor
 Date 7-07
 Drawn by KE
 No. 07-192-B