

SURVEYORS NARRATIVE:

THE PURPOSE OF THIS SURVEY IS TO STAKE THAT TRACT OF LAND DEEDED TO GREG HUMPHREYS, SUCCESSOR TRUSTEE OF THE JAMES F. AND BESSIE A. HUMPHREYS RECORDABLE LIVING TRUST RECORDED ON DOCUMENT # 2009-5560531, UMATILLA COUNTY DEED RECORDS, IN PREPARATION FOR A PARTITION PLAT. ALSO TO STAKE THE PROPERTY TO THE WEST WHICH BELONGS TO CARMACK, AS SHOWN, TO SEE HOW THE FENCES LIE IN RELATION TO THE DEED LINES.

I SURVEYED THE WEST LINE OF WINELAND'S TRACT 3 IN A 1979 SURVEY FOR BAIRD. I ALSO SURVEYED THE EAST LINE OF PARTITION PLAT 1999-55 AND SHOWED THE FENCE AS BEING 9 FEET ONTO CARMACK. IN THAT 1999 PARTITION PLAT I USED ABOUT 10 IRON PIPE MONUMENTS WHICH MATCHED THE DEEDS OF THE MAJORITY THE TRACTS LYING IN THE NW 1/4 OF THE NE 1/4 OF SECTION 6. SEE SAID PARTITION PLAT 1999-55 FOR MORE DETAIL. IN THAT 1999 PARTITION PLAT THE MONUMENTS USED FOR THE NORTH LINE OF SAID NE 1/4 WERE ABOUT 14 FEET NORTH OF THE REVISED MONUMENTS WHICH ARE IN PLACE TODAY. FOR THIS SURVEY I USED THE MONUMENTS WHICH ARE IN PLACE TODAY FOR THE NORTH LINE OF SAID NW 1/4 OF SAID NE 1/4 BECAUSE THEY FIT THE FENCES WHICH RUN ALONG THE NORTH LINES OF HUMPHREYS AND CARMACK MUCH BETTER THAN THE OLD IRON PIPES.


I USED A TOPCON HIPER+ G.P.S. TO CONDUCT THIS SURVEY.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
9 5 1
RENEWS 12/31/2009

- LEGEND:**
- FOUND MONUMENTS AS NOTED OR
 - Ⓐ 5/8" IRON REBAR ME PARTITION PLAT 1999-55
 - Ⓑ 3/4" IRON PIPE, ONE OF 10 FOUND AND USED IN P. PLAT 1999-55, SEE NARR. ALSO CALLED FOR IN ROGERS DEED B. 218, P. 470.
 - SET 5/8"x30" IRON REBAR WITH PLASTIC CAP #951
 - COMPUTED LOCATION
 - P — P — OVERHEAD POWER LINE
- (000) OF RECORD, PARTITION PLAT 1999-55
[000] OF RECORD, "SATHER SUBDIVISION"



SURVEY FOR HUMPHREYS & CARMACK
IN NE 1/4, NE 1/4, SEC. 6, T 4 N,
R 29 E, W.M., UMATILLA COUNTY, OREGON
9/18/09 JOB# S0907065A
EDWARDS SURVEYING P.O. BOX 763
541-567-3336 HERMISTON, OREGON 97838
DRAWN BY JMC

11-09
KK
09-168-B