



REFERENCE MATERIAL

Umatilla County Monumentation Records
 Survey Number 03-274-C (M-045-C)
 Survey Number F-24-Ax
 Survey Number 06-62-Ax
 Survey Number 83-140-C
 Survey Number 97-156-B
 ODOT Strip Map 8B-35-26

Field Notes from GLO Contract dated May 4, 1887,
 executed by James P. Currin and James E. Noland

DEED REFERENCES

Micofilm Document Number 2013-6120651
 Micofilm Document Number 2013-6120653

BASIS OF BEARING

True geodetic North at the Southwest corner of Section 19,
 Township 1 North, Range 35 East of the Willamette Meridian,
 as determined by GPS observation

SCALE: 1" = 600'

LEGEND

- Found monument as described, marked as per Umatilla County Monumentation Records.
- Found 2 1/2" Brass cap set in concrete as per ODOT strip map 8B-35-26
- ⊙ Set 5/8"x30" iron pin rebar with 2 1/2" aluminum cap, marked as per Umatilla County Monumentation Records, filed separately
- Set 5/8"x30" iron pin rebar with plastic cap marked BGB SURVEY MARKER
- () Record measurement as per GLO Special Instructions dated May 4, 1887, executed by Noland and Currin
- [] Record measurement as per Survey Number 03-274-C (M-045-C)
- < > Record measurement as per Survey Number F-24-Ax
- Fence post set on line
- x— Fence

NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted select property corners set and the line marked with paint and flagging in preparation for a timber harvest. I recover the monuments as shown hereon. I subdivide the section as per BLM Manual of Instructions 2009. I establish the highway right of way as per ODOT Strip Map 8B-35-26. Record distances between stationed brass caps differ from measured distances. I hold the brass caps at stations 761+23.52 and 781+06.79 and hold the record alignment as per said strip map. This alignment is very harmonious with the monuments on the ground and the stationing up to the Equation at 708+09.36. North of this, the stationing differs from the strip map. Fencelines on the West side of the property run West, approx. 10-20 feet and on the North side run true along the West half, but fall South of line approx. 13-25 feet along the East half of the posted line. I find no other unusual conditions with this survey.

RECEIVED BY

Umatilla County Surveyor
 Date: 9/25/19
 Rec'd By: CT
 No.: 19-097-B

REGISTERED PROFESSIONAL LAND SURVEYOR
 JEFFREY S. HSU
 83571
 Renewal Date: June 30, 2021

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey	
Situate in Section 33, Township 1 North, Range 35 East of the Willamette Meridian	
UMATILLA COUNTY, OREGON	
SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 600'	Drawn by: J. S. H. Sept. 2019